

SURVEY &
REMONUMENTATION

LIBER 15212 PG 854

JAN 20 95 011168

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE

OK - T. SMITH

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Oakland

COMMISSION

Located In: Orion
Twp.

Corner Code #H

- | | | | | | |
|---------------------------------------|---|----|---|-----|-----|
| 1. Public Land Survey | T | 4N | R | 10E | H-9 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling
in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous
Property in Sec. | S | | T | R | |
| | S | | T | R | |

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
20 JAN 95 7:26 A.M. RECEIPT# 5B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 9-14-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Huston K. Kennedy, in a field survey on September 20, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post; 10" White Oak N70°E 51 Links; 4" Black Oak S72°W 32 Links
1.) 1984-Ward, P.S. #22445; LCRC L.8854, Pg.42 - Fnd Iron Pipe
2.) 1984-Ward, P.S. #22445; Unrecorded Survey - Fnd Iron Pipe, used same wit as 1984 LCRC
3.) 1992-Kennedy, P.S. #17623; Unrecorded Survey - Fnd 1/2" Iron Pipe in East-West fence & tree row

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Pipe flush with the ground in a fence-tree line extending to the East & West.

Witnesses from LCRC #1 were used to recover and verify the location of the found 1/2" Iron Pipe.

I accept the found 1/2" Iron Pipe as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-9 I replaced the found 1/2" Iron Pipe with 1/2" Iron Rod encased in a 4" diameter concrete cylinder 36" long w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623.
Due West 8.41' Set PK & Remon. Washer North face 10" Ash
Due East 6.47' Set PK & Remon. Washer South face 24" Ash
S15°W 20.25' Set PK & Remon. Washer SE face 8" Oak
N87°W 19.21' Set PK & Remon. Washer North face 12" Cherry

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature]
Surveyor's Michigan License No. 17623

Date December 17, 1994

