

Dec 29 1994 3 25 982

SURVEY & REMONUMENTATION

LIBER 15175 Pt 142

OK - T. SMITH

LAND CORNER RECORDATION CERTIFICATE

MAY - 1 1995

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland COMMISSION Located In: Orion Corner Code #
(County) Twp.

1. Public Land Survey	T	<u>4N</u>	R	<u>10E</u>	H-11
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

7.00 MISCELLANEOUS RECORDING
 \$ 2.00 REMONUMENTATION
 29 DEC 94 9:47 A.M. RECEIPT# 46B
 PAID RECORDED - OAKLAND COUNTY
 LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with
 ACT 345, P.A. 1990

APPROVED ON: 9-14-94
 OAKLAND COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Huston K. Kennedy, in a field survey on August 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	16	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post; 36" White Oak S57*W 72 Links; 6" Black Oak N53*E 32 Links
- 1.) 1980-O'Rourke, P.S. #16937; LCRC L.7771, Pgs.609 & 610 - Fnd 5/8" Iron Bar
- 2.) 1989-Bongiovanni, P.S. #24586; LCRC L.11191, Pg.418 - Fnd Iron Pipe
- 3.) 1991-Hoben, P.S. #35994; LCRC L.12236, Pg.224 - Fnd 1/2" Iron Monument Box
- 4.) 1989-Bongiovanni, P.S. #24586; Survey L11217, Pg.683 & 683 - Fnd Iron Pipe, same wit as 1989 LCRC

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Rod in a Monument Box 1.95' North of the construction joint for the West bound lane of Silver Bell Road, which has a concrete surface, 4.25' West to the centerline of Giddings North, Which has a gravel surface, also due South of entrance to the Orion Plant.

Witnesses from LCRC #1 & 2 were used to recover and verify the location of the 1/2" Iron Rod in a Monument Box.

I accept the found 1/2" Iron Rod in a Monument Box as the best evidence of the original corner position.

*710
2100
File*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-11 I replaced the 1/2" Iron Rod with a 5/8" x 24" Iron Rod w/2" diameter cap stamped Oakland County Remonumentation, PS #17623 in a existing Monument Box.
- N49°W 53.95' Set PK & Remon. Washer SW face Power Pole
- N33°E 71.06' Set PK & Remon. Washer NW face 27" Walnut
- S70°E 207.09' Set PK & Remon. Washer NE face Power Pole
- S44°W 110.16' Set PK & Remon. Washer SE face Power Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by [Signature]
 Surveyor's Michigan License No. 17623

Date December 3, 1994