

**SURVEY & REMONUMENTATION**

LIBER 15225 PG 656

JAN 27 1995 016442

MAY - 1 1995

**LAND CORNER RECORDATION CERTIFICATE** 7.00 MISCELLANEOUS RECORDING  
**COMMISSION** Filing Requirement of Act 74, Mich. P.A. 1970 2.00 REMONUMENTATION

For corners in  
Oakland  
(County)

Located In: Orion Twp. Corner Code #H-13

- |                                    |             |              |             |
|------------------------------------|-------------|--------------|-------------|
| 1. Public Land Survey              | T <u>4N</u> | R <u>10E</u> | <u>H-13</u> |
|                                    | T _____     | R _____      | _____       |
|                                    | T _____     | R _____      | _____       |
|                                    | T _____     | R _____      | _____       |
| 2. Property Controlling in Section | S _____     | T _____      | R _____     |
|                                    | S _____     | T _____      | R _____     |
| 3. Miscellaneous Property in Sec.  | S _____     | T _____      | R _____     |
|                                    | S _____     | T _____      | R _____     |

27 JAN 95 11:01 A.M. RECEIPT# 76B  
 PAID RECORDED - OAKLAND COUNTY  
 LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

OK - T. SMITH

Compliance with  
 ACT 345, P.A. 1990

APPROVED ON: 12-29-94  
 OAKLAND COUNTY REMONUMENTATION  
 PEER GROUP COMMITTEE  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Huston K. Kennedy, in a field survey on December 20, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1817-GLO Wampler, D.S.; No Post - In Lake - No Witnesses  
 1.) 1978-Lippincott, P.S. #25855; LCRC L.7372, Pg.854 - Fnd 5/8" Re-rod in Monument Box  
 2.) 1980-O'Rourke, P.S. #16937; LCRC L.7771, Pg.608 - Fnd 1" Iron Bar in Monument Box  
 3.) 1990-Wozniak, P.S. #15066; LCRC L.11580, Pg.542 - Fnd Iron w/cap #16937

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Rod in a Monument Box in the centerline of the East bound lanes of Brown Road, which has a concrete surface. Found second 1/2" Iron Rod in a Monument Box 59.47' due West in the centerline of Giddings Road to the South, which is the North 1/4 corner of Section 3, T3N, R10E, (H-1).

Witnesses from LCRC #3 were used to recover and verify the location of the found 1/2" Iron Rod in a Monument Box.

I accept the found 1/2" Iron Rod in a Monument Box as the best evidence of the original corner position.

**FIELD MEASUREMENT BETWEEN**

- H-13 to G-13 2681.66 Ft. (L.7766, Pg.179)  
 H-13 to I-13 2724.09 Ft. (L.7766, Pg.179)  
 H-13 to H-3 59.47 Ft. (Pontiac Twp.)

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- H-13 I replaced the found 1/2" Iron Rod with a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623  
 N52°W 124.45' Set PK & Remon. Washer South face Power Pole  
 N65°E 178.20' Set PK & Remon. Washer SE face Power Pole  
 S78°W 115.17' Set PK & Remon. Washer South face Power Pole  
 S05°W 37.09' Set PK & Remon. Washer East face Power Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by Huston K. Kennedy  
 Surveyor's Michigan License No. 17623

Date January 18,