

LAND CORNER RECORDATION CERTIFICATE

OK - T. SMITH

For corners in Oakland  
(County)

Filing Requirement of Act 74, Mich. P.A. 1970 7.00 MISCELLANEOUS RECORDING

\$ 2.00 REMONUMENTATION  
20 JAN 95 7:26 A.M. RECEIPT# 58  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

	Located In:	Orion Twp.	Corner Code #:	<u>I-7</u>
1. Public Land Survey	T <u>4N</u>	R <u>10E</u>		
	T	R		
	T	R		
	T	R		
2. Property Controlling in Section	S	T	R	
	S	T	R	
3. Miscellaneous Property in Sec.	S	T	R	
	S	T	R	

Compliance with ACT 345, P.A. 1990

APPROVED ON: 9-21-94  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Huston K. Kennedy, in a field survey on October 20, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1817-GLO Wampler, D.S.; Set Post 24" Black Oak S15\*W 48 Links; 24" Black Oak N16\*B 32 Links  
1.) 1973-Stonerock, P.S. #13601; LCRC L.6083, Pg.36 - Fnd 1/2" Iron Rod  
2.) 1976-Kennedy, P.S. #17623; LCRC L.6821, Pg.467 - Fnd 1/2" Iron rod

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Rod 4' North of the centerline of Scripps Road, which has a grave surface extending to the East & West and 4' West to the centerline of a driveway to the North.

Witnesses from LCRC #2 were used to recover and verify the location of the found 1/2" Iron Rod.

I accept the found 1/2" Iron Rod as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-7 I replaced the found 1/2" Iron Rod with a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623.

N44°E 29.20' Set PK & Remon. Washer SE face 21" Hickory  
N56°W 37.91' Set PK & Remon. Washer SW face 12" Hickory  
S07°W 23.27' Set PK & Remon. Washer East face clump Oak  
S31°E 32.57' Set PK & Remon. Washer NE face 17" Ash

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by [Signature]  
Surveyor's Michigan License No. 17623

Date December 23, 1994