

**SURVEY &  
REMONUMENTATION**

LIBER 15225 PG 657

JAN 27 1995 016443

MAY - 1 1995

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

\$ 7.00 MISCELLANEOUS RECORDING  
\$ 2.00 REMONUMENTATION  
27 JAN 95 11:01 A.M. RECEIPT# 76B  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

For corners in

**COMMISSION**

<u>Oakland</u> <small>(County)</small>	Located In: Orion Twp.	Corner Code # I-8
1. Public Land Survey	T <u>4N</u> R <u>10E</u>	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

**OK - T. SMITH**  
Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 12-29-94  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

I, Huston K. Kennedy, in a field survey on December 20, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

A. Description of original monument and accessories and/or subsequent restoration:

1817-GLO Wampler, D.S.; Set Post; 10" White Oak S58°E 7 Links; 4" Black Oak N79°W 40 Links  
There are no recorded LCRC's or recorded or unrecorded Certificates of Survey for this corner

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Rod 2" above ground with a fence line extending South, East, West and 29 feet North to a plowed field.

The description to the East was used to verify the location of the found 1/2" Iron Rod

FIELD MEASUREMENTS BETWEEN

I-8 to J-8 1985.91 Ft.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-8 I replaced the found 1/2" Iron Rod with 1/2" Iron Rod encased in a 4" diameter concrete cylinder 36" long w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623.  
Due South 2.40' Set PK & Remon. Washer West face 27" Hickory  
S13°W 26.72' Set PK & Remon. Washer West face 11" Elm  
S88°W 16.70' Set PK & Remon. Washer South face 36" Oak  
S88°E 12.89' Set PK & Remon. Washer North face 8" Elm

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best position of the original corner.



Signed by Huston K. Kennedy  
Surveyor's Michigan License No. 17623

Date January 12, 1995