

SURVEY & REMONUMENTATION

LIBR 15150 PG 485

Dec 15 94 3 16 4 18

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE

Compliance with ACT 345, P.A. 1990

Filing Requirement of Act 74, Mich. P.A. 1970

APPROVED ON: 9-21-94
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

For corners in
Oakland
(County)

COMMISSION

Located In: Orion
Twp.

Corner Code #

1. Public Land Survey	T	4N	R	10E	I-11
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

\$ 7.00 MISCELLANEOUS RECORDING

\$ 2.00 REMONUMENTATION

15 DEC 94 10:41 A.M. RECEIPT# 25B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

OK - T. SMITH

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Huston K. Kennedy, in a field survey on August 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	I
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post; 13" White Oak S27°E 1.60 Chains; 12" White Oak N44°W 81 Links
- 1.) 1980-O'Rourke, P.S. #16937; LCRC L.7771, Pgs.609-610 - Fnd 5/8" Iron Bar.
- 2.) 1980-Petric, P.S. #19841; LCRC L.7835, Pg.883 - Fnd 5/8" Rod
- 3.) 1985-Buckerfield, P.S. #10868; LCRC L.8950, Pg.181 - Fnd 1/2" Iron in Monument Box
- 4.) 1989-Bongiovanni, P.S. #24586; LCRC L.11191, Pg.419 - Fnd Iron Rod
- 5.) 1990-Newman, P.S. #24607; LCRC L.11604, Pg.641 - Fnd Iron in Monument Box
- 6.) 1989-Bongiovanni, P.S. #24586; Survey L.11217, Pg.682 - Fnd Iron Rod, used same wit as 1989 LCRC

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron in a Monument Box in the centerline of Silver Bell Road, which has a concrete surface and 240' East of the entrance to Eagle Valley Disposal.

Witnesses from LCRC #3 were used to recover and verify the location of the found 1/2" Iron in a Monument Box.

I accepted the found 1/2" Iron Rod in a Monument Box as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-11 I replaced the found 1/2" Iron Rod with a 5/8" x 24" Iron rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623 in a existing Monument Box.
- N14°E 62.03' Set PK & Remon. Washer SE face Power Pole
- N75°E 221.54' Set PK & Remon. Washer South face Power Pole
- N76°W 277.54' Set PK & Remon. Washer South face Power Pole
- S75°W 279.07' Set PK & Remon. Washer SE face Power Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of position of the original corner.



Signed by Huston K. Kennedy
Surveyor's Michigan License No. 17623

Date December 3, 1994