

**SURVEY & REMONUMENTATION**

LIBER 14960 PG 095

94 242125

MAY - 1 1995

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

\$ 7.00 MISCELLANEOUS RECORDING  
 \$ 2.00 REMONUMENTATION  
 8 SEP 94 3:16 P.M. RECEIPT# 1341  
 PAID RECORDED - OAKLAND COUNTY  
 LYNN D. ALLEN, CLERK/REGISTER OF DEED

For corners in

Oakland COMMISSION  
(County)

Located In: Orion Corner Code #  
Township

1. Public Land Survey	T	<u>4</u>	N	<u>10</u>	E	<u>K-3</u>
	T		R			
	T		R			
	T		R			
2. Property Controlling in Section	S		T		R	
	S		T		R	
3. Miscellaneous Property in Sec.	S		T		R	
	S		T		R	

OK - T. SMITH

Compliance with ACT 345, P.A. 1990

APPROVED ON: 1-5-94  
 OAKLAND COUNTY REMONUMENTATION  
 Register of Deeds Stamp # 1111 File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Huston K. Kennedy, in a field survey on November 18, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K
2		6	5		4		3		2		
3											
4		7	8	9	10	11					
5											
6		16	17	18	15	14					
7											
8		19	20	21	22	23					
9											
10		30	29	28	27	26					
11											
12		31	32	33	34	35					
13											

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

1817-GLO Wampler, D.S.; Set Post; 36" White Oak N29 1/2°E 53 Lnks; 6" White Oak S67°W 98 Lnk  
 1973-Hubbell, P.S. #12022; LCRC L.6701, Pg.45-46 - Fnd concrete monument  
 1983-Kapelczak, P.S. #24598; LCRC L.8335, Pg.575 - Fnd concrete monument

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1993 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd a square concrete monument with a 3/4 Iron Pipe. There is a tree line extending to the South.

Witness points from the 1973 LCRC and 1983 LCRC were found and they were used to recover and verify the found square concrete monument with 3/4" Iron Pipe.

I accepted the found square concrete monument as the best evidence of the original corner position.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

K-3 I replaced the found square concrete monument with 3/4" iron pipe with a 4" diameter concrete monument 36" long with a 2" diameter cap stamped Oakland County Remonumentation P.S. #17623.

N15°E-45.81 ft-Set PK/Remon. Tag West face 8" Maple  
 N85°W-5.38 ft-Set PK/Remon. Tag SW face 10" Spruce  
 S45°W-7.33 ft-Set PK/Remon. Tag NW face 10" Spruce  
 Due South-55.46 ft-Set PK/Remon. Tag East face Power Pole

The selected location is accepted by me and is generally accepted by \_\_\_\_\_ as the best available evidence of the position of the original position.



Signed by H.K. Kennedy  
 Surveyor's Michigan License No. 17623

Date June 22, 1994