

**SURVEY &
REMONUMENTATION**

LIBER 14960 PC 096

94 242426

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

OK - T. SMITH

For corners in MAY - 1 1995

Oakland (County) **COMMISSION** Located In: Orion Township Corner Code #

1. Public Land Survey	T <u>4</u> N R <u>10</u> E	<u>K-4</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
8 SEP 94 3:17 P.M. RECEIPT# 1348
PAID RECORDED - OAKLAND COUNT
LYNN D. ALLEN, CLERK/REGISTER OF DEED
Compliance with
ACT 345, P.A. 1990

APPROVED ON: 1-5-94
OAKLAND COUNTY REMONUMENTATION
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2						
3											
4	7	8	9	10	11						
5											
6	18	17	16	15	14						
7											
8	19	20	21	22	23						
9											
10	30	29	28	27	26						
11											
12	31	32	33	34	35						
13											

I, Huston K. Kennedy, in a field survey on December 16, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1817-GLO Wampler, D.S.; Set Post; 12" White Oak West 55 Lnks; 24" White Oak N45°E 106 Lnks
1987-Fenn, P.S. #23505; LCRC L.9856, Pg.168 - Fnd 1" Iron

Handwritten initials/signature

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd a 1" iron pipe.

The witness trees are still existing, but the witness points are grown over. They were used to recover and verify the found 1" iron pipe.

I accepted the found 1" iron pipe as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-4 I replaced the found 1" iron pipe with a 4" diameter concrete monument 36" long with a 2" diameter cap stamped Oakland County Remonumentation P.S. #17623.

- N05°E-57.87 ft-Set PK & Remon. Washer East face 12" Oak
- N30°W-43.79 ft-Set PK & Remon. Washer NE face 13" Oak
- N80°E-34.29 ft-Set PK & Remon. Washer South face 6" Oak
- S10°W-29.57 ft-Set PK & Remon. Washer West face 9" Pine

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original position.



Signed by Huston K. Kennedy
Surveyor's Michigan License No. 17623

Date June 22, 1994