

**SURVEY &
REMONUMENTATION**

LIBER **15225** PGC **660**

JAN 27 95 016446

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

OK - T. SMITH
MISCELLANEOUS RECORDING

For corners in
Oakland

COMMISSION

Located In: **Orion**
Twp.

Corner Code **#**

\$ 7.00
\$ 2.00
27 JAN 95 11:02 A.M. RECEIPT# 76B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 9-21-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

1. Public Land Survey	T	4N	R	10E	K-8
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Huston K. Kennedy in a field survey on December 20, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1817-GLO Wampler, D.S.; Set Post; 24" White Oak S27°E 1.06 Chains
1.) 1989-Dunn, P.S. #28408; LCRC L.10990, Pg.009 - Fnd 1/2" Iron Rod

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd Concrete Monument on a state land trail running North-South, the corner falls on the West side of the trail, and South of house #2443 and North of house #2429.

Witnesses from LCRC #1 were used to recover and verify the location of the found Concrete Monument.

I accept the found Concrete Monument as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-8 I placed 2" diameter brass cap stamped Oakland County Remonumentation, PS #17623 on the existing 4" Concrete Monument
S62°W 26.90' Set PK & Remon. Washer SE face 12" Cherry
S51°E 20.02' Set PK & Remon. Washer NE face 10" Sasafraass
N43°E 24.25' Set PK & Remon. Washer SE face 31" Oak
N37°W 24.79' Set PK & Remon. Washer NE face 11" Sasafraass

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by [Signature]
Surveyor's Michigan License No. 17623

Date January 16, 1995

	A	B	C	D	E	F	G	H	I	J	K	L	P
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Handwritten notes:
17623
1/16/95