

SURVEY &  
REMONUMENTATION

LIGER 15225PG661

JAN 27 1995 016447

MAY - 1 1995 LAND CORNER RECORDATION CERTIFICATE 7.00 MISCELLANEOUS RECORDING

Filing Requirement of Act 74, Mich. P.A. 1970 2.00 REMONUMENTATION

For corners in

COMMISSION

27 JAN 95 11:02 A.M. RECEIPT# 76B  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Oakland (County) Located In: Orion Twp. Corner Code #  
1. Public Land Survey T 4N R 10E K-9  
T R  
T R  
T R  
2. Property Controlling S T R  
in Section S T R  
3. Miscellaneous S T R  
Property in Sec. S T R

OK - T. SMITH

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 9-21-94  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Huston K. Kennedy, in a field survey on December 20, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post; 12" White Oak S14\*E 36 Links; 24" White Oak N32\*W 1.31 Chains  
1.) 1988-Buckerfield, P.S. #10868; LCRC L.10292, Pg.94 - Set 1/2" Iron Rod  
2.) 1989-Dunn, P.S. #28408; LCRC L.10990, Pg.009 - Fnd 1/2" Iron Rod w/cap #18068  
3.) 1987-Buckerfield, P.S. #10868; Unrecorded Survey - Fnd 1/2" Iron Rod, used same wit as 1988 LCRC

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Rod capped #10868 ground level 25' ± to the centerline of Bal Mountain Road. (Unimproved)

Witnesses from LCRC #1 & 2 were used to recover and verify the location of the found 1/2" Iron Rod.

I accept the found 1/2" Iron Rod w/cap #10868 as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-9 I replaced the found 1/2" Iron Rod with a 1/2" Iron Rod encased in a 4" diameter concrete cylinder 36" long w/2" diameter bra cap stamped Oakland County Remonumentation, PS #17623.  
N10°W 20.55' Set PK & Remon. Washer East face 10" clump Maple  
S77°E 73.28' Set PK & Remon. Washer North face 24" Oak  
S71°W 23.95' Set PK & Remon. Washer SE face 12" Cherry  
S17°W 34.58' Set PK & Remon. Washer West face 10" Oak

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of position of the original corner.



Signed by [Signature]  
Surveyor's Michigan License No. 17623

Date January 16, 1995