

SURVEY &
REMONUMENTATION

LIBER 13127 PG 279

Dec 294307772
Compliance with
ACT 345, P.A. 1990

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

APPROVED ON: 9-21-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

For corners in

Oakland
(County)

COMMISSION

Located In: Orion
Twp. Corner Code #:

- | | | | |
|---------------------------------------|------|-------|------|
| 1. Public Land Survey | T 4N | R 10E | K-12 |
| | T | R | |
| | T | R | |
| | T | R | |
| 2. Property Controlling
in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous
Property in Sec. | S | T | R |
| | S | T | R |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
2 DEC 94 3:12 P.M. RECEIPT# 127B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

OK - T. SMITH
Register of Deeds Stamp & File Number

I, Huston K. Kennedy, in a field survey on August 12, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post; 24" White Oak N59°E 49 Links; 12" Hickory S51°W 64 Links
- 1.) 1986-Kennedy, P.S. #17623; LCRC L.9397, Pg.258 - Fnd 3/4" Iron Pipe
 - 2.) 1987-Buckerfield, P.S. #10868; LCRC L.9803, Pg.551 - Fnd 3/4" Iron Pipe
 - 3.) 1987-Kennedy, P.S. #17623; LCRC L.9958, Pg.261 - Fnd 3/4" Iron Pipe, used same wit as 1986 LCRC
 - 4.) 1990-Buckerfield, P.S. #10868; LCRC L.11264, Pg.350 - Fnd 3/4" Iron Pipe
 - 5.) 1992-Ward, P.S. #22445; LCRC L.12976, Pg.727 - Monument
 - 6.) 1987-Kennedy, P.S. #17623; Survey L.13027, Pg.135 - Fnd 3/4" Iron Pipe, used same wit as 1986 LCRC
 - 7.) 1987-Kennedy, P.S. #17623; Survey L.13931, Pg.271 - Fnd 3/4" Iron Pipe, used same wit as 1986 LCRC
 - 8.) 1990-Kennedy, P.S. #17623; Survey L.12791, Pg.721 - Fnd 3/4" Iron Pipe, used same wit as 1986 LCRC

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd Concrete Monument 1' ± above surface. The Concrete Monument is at the base of a 1' wooden fence post with fence lines extending South & West.

Witnesses from LCRC #1 were used to recover and verify the location of the found Concrete Monument.

I accepted the found Concrete Monument as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-12 I placed a 2" brass cap stamped Oakland County Remonumentation, PS #17623 on the found Concrete Monument.
Due South 12.40' Set PK & Remon. Washer East face 9" Elm
N85°E 6.61' Set PK & Remon. Washer South face 24" Hickory
N12°W 5.04' Set PK & Remon. Washer East face 28" Hickory
S53°E 10.95' Set PK & Remon. Washer SW face 12" Hickory

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence position of the original corner.

Signed by

Huston K. Kennedy

Date

October 31,

Surveyor's Michigan License No.

17623



	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Handwritten notes: 7.00, 2.00, and other illegible scribbles.