

**SURVEY &
REMONUMENTATION**

LIBER 14960 PG 098

MAY - 1 1995 **LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

94 242428
OK - T. SMITH

For corners in

COMMISSION

Oakland
(County)

Located In: Orion Corner Code #
Township

- | | | | | | | | |
|---------------------------------------|---|----------|---|---|-----------|---|------------|
| 1. Public Land Survey | T | <u>4</u> | N | R | <u>10</u> | E | <u>L-3</u> |
| | T | | R | | | | |
| | T | | R | | | | |
| | T | | R | | | | |
| 2. Property Controlling
in Section | S | | T | | R | | |
| | S | | T | | R | | |
| 3. Miscellaneous
Property in Sec. | S | | T | | R | | |
| | S | | T | | R | | |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
8 SEP 94 3:17 P.M. RECEIPT# 134B
PAID RECORDED - OAKLAND COUNT
LYNN D. ALLEN, CLERK/REGISTER OF DEED

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 1-5-94
OAKLAND COUNTY REMONUMENTATION
REGISTER OF DEEDS STAMP & FILE NUMBER

I, Huston K. Kennedy in a field survey on November 18, 19 93
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1817-GLO Wampler, D.S.; Set Post; 10" White Oak N15°W 87 Lns; 10" White Oak S56°E 1.01 Lnk
1973-Buckerfield, P.S. #10868; LCRC L.6222, Pg.566-567 - Fnd a concrete monument
1977-Kennedy, P.S. #17623; LCRC L.7037, Pg.884 - Fnd a concrete monument
1980-Heil, P.S. #18993; LCRC L.7739, Pg.893-894 - Fnd a concrete monument
1987-Fenn, P.S. #23505; LCRC L.9856, Pg.170 - Fnd a concrete monument

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd a concrete monument.

The witness trees are still existing, but the witness points were grown over. They were
used to recover and verify the found concrete monument.

I accepted the found concrete monument as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the original corner:

L-3 I replaced the found concrete monument with a 4" diameter concrete monument with
a 2" diameter cap stamped Oakland County Remonumentation P.S. #17623
N20°W-7.98 ft-Set PK/Remon. Tag North face 9" Cherry
Due West-6.69 ft-Set PK/Remon. Tag South face 11" Cherry
Due East-19.72 ft-Set PK/Remon. Tag South face 8" & 4" Twin Oak
S05°W-9.25 ft-Set PK/Remon. Tag NW face 17" Oak

The selected location is accepted by me and is generally accepted by Professional Surveyors
as the best available evidence of the position of the original position.

Signed by Huston K. Kennedy Date June 22, 1994
Surveyor's Michigan License No. 17623

