

**SURVEY &  
REMONUMENTATION**

LIBER **14960** PG **099**

**94 242429**

**MAY - 1 1995**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

**COMMISSION**

**OK - T. SMITH**

<u>Oakland</u> <small>(County)</small>	Located In: Orion Township	Corner Code # <u>L-5</u>
1. Public Land Survey	T <u>4</u> N R <u>10</u> E	<u>L-5</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

**\$ 7.00 MISCELLANEOUS RECORDING  
\$ 2.00 REMONUMENTATION**  
**8 SEP 94 3:17 P.M. RECEIPT# 1341**  
**PAID RECORDED - OAKLAND COUNTY**  
**LYNN D. ALLEN CLERK/REGISTER OF DEEDS**  
**ACT 345, P.A. 1990**

APPROVED ON: 1-5-94  
**OAKLAND COUNTY REMONUMENTATION**  
**REGISTER OF DEEDS STAMP & FILE NUMBER**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K
2	6		5		4		3		2		
3											
4	7		8		9		10		11		
5											
6	18		17		16		15		14		
7											
8	19		20		21		22		23		
9											
10	30		29		28		27		26		
11											
12	31		32		33		34		35		
13											

I, Huston K. Kennedy, in a field survey on November 18, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 1817-GLO Wampler, D.S.; Set Post; 10" Black Oak N62°E 55 Lns; 11" White Oak S54°W 1.20 Lnk  
 1985-Kennedy, P.S. #17623; LCRC L.9000, Pg.572 - Fnd 1/2" Iron Rod  
 1987-Fenn, P.S. #23505; LCRC L.9856, Pg.170 - Same wits as 1985 LCRC

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 1993 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd a concrete monument located 9' Nor of the center of Clarkston Road, which is gravel surface.  
 The witness points from the 1985 LCRC are still existing and they were used to recover & verify the found concrete monument.  
 I accepted the found concrete monument as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 L-5 I found concrete monument and placed a 2" diameter cap stamped Oakland Remonumentation P.S. #17623.  
 S05°E-36.56 ft-Set PK & Remon. Washer West face 33" Oak  
 S17°W-34.13 ft-Set PK & Remon. Washer East face 10" Locust  
 N10°W-28.27 ft-Set PK & Remon. Washer East face 13" Maple  
 N70°E-41.57 ft-Set PK & Remon. Washer SE face 4" - 8" Triple Elm  
 The selected location is accepted by me and is generally accepted by \_\_\_\_\_ as the best available evidence of the position of the original position.



Signed by Huston K. Kennedy Date June 22, 1994  
 Surveyor's Michigan License No. 17623