

SURVEY & REMONUMENTATION

APR 07 1998

LIBER 17634 PC 847

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SP 29 91231900

For corners in SECTION

Oakland

(County)

Located in Orion Twp.

Corner Code #

1. Public Land Survey	T <u>4N</u> R <u>10E</u>	L-9
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

\$ 9.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
29 SEP 97 12:45 P.M. RECEIPT# 1478
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with ACT 345, P.A. 1990

APPROVED ON: 8-28-97 RS
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Huston K. Kennedy, in a field survey on 8-8, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
1817-GLO Wampler, D.S.; Set Post 6" White Oak N18°W 21 Links; 18" White Oak S27°E 31 Links
1.) 1943 McAlpine, PS #1015; Unrecorded Survey - Fnd post, no witnesses

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1997 Kennedy Surveying, Inc. - Kennedy, PS #17623 - The only evidence that I was able to recover a existing fence line extending to the East, West, North and the intersection is at a 24" Oak.

HOW THE CORNER WAS RECOVERED


I recovered the corner by setting a reference corner in the existing East-West fence line 6.80 feet East of the 24" Oak, which was held as the corner.

Field measurements see back side of LCRC

9.00 FILE
2.00 ✓

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
L-9 I set a 4" diameter Concrete Monument 36" long with 1/2" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623 as a REFERENCE CORNER 6.80 feet East of the corner.
Due West 6.80' Set PK & Remon Washer North face 24" Oak
S56°E 34.88' Set PK & Remon Washer SE face 11" Cherry
N84°W 27.23' Set PK & Remon Washer North face 29" Oak
N47°W 25.91' Set PK & Remon Washer NE face 40" Twin Oak

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by [Signature]
Surveyor's Michigan License No. 17623

Date 8-29-97

SURVEY &
REMONUMENTATION

APR 07 1998

LIBER 17634 PC848

SECTION

FIELD MEASUREMENTS BETWEEN

L-9 to K-9

GLO = 39.16 chains or 2584.56 Ft.

No sidwell or plat distances

GPS-NEA = 2664.28 Ft.

L-9 to M-9

GLO = 39.16 chains or 2584.56 Ft.

Sidwell distance = 2687.86 Ft. (Section 24)

GPS-NEA = 2687.23 Ft.