

SURVEY & REMONUMENTATION COPY

JAN 397001281

LIBER 16874 PG 125

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION For corners in Oakland (County)

Located In: Orion Twp Corner Code #

Table with 5 rows and 4 columns: 1. Public Land Survey, 2. Property Controlling in Section, 3. Miscellaneous Property in Section, 4. Lot No., 5. Private Claims. Columns include T, R, S, and M-1.

\$ 9.00 MISCELLANEOUS RECORDING \$ 2.00 REMONUMENTATION 3 JAN 97 7:46 A.M. RECEIPT# 78 PAID RECORDED - OAKLAND COUNTY LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-17-96 TS OAKLAND COUNTY REMONUMENTATION PIER GROUP

Register of Deeds Stamp & File Number

Grid table with columns A-L and rows 2-13. Contains numbers 6 through 36.

Huston K. Kennedy, in a field survey on 11/6, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post 11" Black Oak S30°W 54 Links; 17" Black Oak N51°E 42 Links
1.) 1994-Ward, PS #22445; L. 15517, Pg.425 Set Concrete Monument w/2" diameter brass cap stamped Oakland County Remonumentation, PS #22445
2.) 1995-Kennedy, PS #17623; L. 15517, Pg. 425 - Fnd Concrete Monument w/2" diameter brass cap stamped Oakland County Remonumentation PS #22445

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1996 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd 4" diameter Concrete Monument w/2" diameter brass cap stamped Oakland County Remonumentation, PS #22445, 3 feet East of the existing centerline of Barr Road extending to the North, which has a gravel surface, and 18 feet South of the existing centerline of Indian Lake Road extending to the East & West, which has a gravel surface. A tree-fence row extending to the South. This corner is being accepted and used as a common corner with the Northwest corner of Section 6, T4N, R11E, Oakland Twp., (A-1); Southwest corner of Section 31, T5N, R11E, Addison Twp., (A-13), also the Southeast corner of Section 36, T5N, R10E, Oxford Twp., (N-13).

Witnesses from LCRC #1 & 2 were used to recover and verify the location of the found 4" diameter Concrete Monument w/2" diameter brass cap stamped Oakland County Remonumentation, PS #22445.

I accepted the found 4" diameter Concrete Monument w/2" diameter brass cap stamped Oakland County Remonumentation, PS #22445 as the best evidence of the original corner position.

Field Measurements see back side of LCRC

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-1 I found a 4" diameter Concrete Monument w/2" diameter brass cap stamped Oakland County Remonumentation, PS #22445
N73°E 18.63' Fnd PK Nail & Brass Disc. #22445 North face 18" Elm
S10°E 24.45' Fnd PK Nail & Brass Disc. #22445 E face Utility Pole
N41°W 85.16' Fnd PK Nail & Brass Disc. #22445 SW face 6" Box Elder
N31°E 90.57' Fnd PK Nail & Brass Disc. #22445 SE face Utility Pole
South 32.91' Found Concrete Monument

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature] Surveyor's Michigan License No. 17623

Date 12-18-96



COPY

LIBER 16874 PG 126

FIELD MEASUREMENTS BETWEEN

M-13 to L-13 GLO = 40 chains or 2640.00 Ft., 2624.55 Ft.
M-13 to M-12 GLO = 40 chains or 2640.00 Ft., 2642.75 Ft.

SURVEY &
REMONUMENTATION

MAY 22 1897

COMMISSION