

**SURVEY &  
REMONUMENTATION**

LIBER **14960** PG **100**

MAY - 1 1995

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**94 242430**

OK - T. SMITH

For corners in **COMMISSION**  
Oakland  
(County)

Located in: Orion Corner Code #  
Township

1. Public Land Survey	T	4	N	R	10	E	M-4
	T			R			
	T			R			
	T			R			
2. Property Controlling in Section	S			T			
	S			T			
3. Miscellaneous Property in Sec.	S			T			
	S			T			

\$ 7.00 MISCELLANEOUS RECORDING  
\$ 2.00 REMONUMENTATION  
8 SEP 94 3:17 P.M. RECEIPT# 1349  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS  
Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 15-94  
OAKLAND COUNTY REMONUMENTATION  
Register of Deeds Stamp File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Huston K. Kennedy, in a field survey on November 18, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2							
3												
4	7	8	9	10	11							
5												
6	18	17	16	15	14							
7												
8	19	20	21	22	23							
9												
10	30	29	28	27	26							
11												
12	31	32	33	34	35							
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

1817-GLO Wampler, D.S.; Set Post; 12" White Oak N72°E 48 Lnks; 13" White Oak N72°W 42 Lnks  
1987-Fenn, P.S. #23505; LCRC L.9856, Pg.168 - Fnd Iron in monument box

*Handwritten initials/signature*

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1993 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" iron rod in a monument box locat 3.5' South of the centerline of Stoney Creek Road, which is bituminous surface.

All witness points from the 1987 LCRC were still existing and they were used to recover a verify the found 1/2" iron rod in a monument box.

I accepted the found 1/2" iron rod in a monument box as the best evidence of the origin corner position.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

M-4 I replaced the found 1/2" iron rod in a monument box with a 5/8" x 24" iron rod with a diameter cap stamped Oakland County Remonumentation P.S. #17623.

- N40°E-41.46 ft-Set PK & Remon. Washer SE face 7" Locust
- N03°E-35.90 ft-Set PK & Remon. Washer West face 7" Locust
- N20°E-38.37 ft-Set PK & Remon. Washer East face 6" Locust
- N45°W-58.36 ft-Set PK & Remon. Washer NE face 10" Locust

The selected location is accepted by me and is generally accepted by Profest and Surveyors as the best available evidence of the position of the original position.



Signed by Huston K. Kennedy  
Surveyor's Michigan License No. 17623

Date June 22, 1994