

**SURVEY &  
REMONUMENTATION**

MAY - 1 1995

LIBER **14960** of **101**

**LAND CORNER RECORDATION CERTIFICATE**

94 **242431**

**COMMISSION**

Filing Requirement of Act 74, Mich. P.A. 1970

OK - T. SMITH

For corners in

<u>Oakland</u> <small>(County)</small>	Located In: <u>Orion</u> Township	Corner Code # <u>M-5</u>
1. Public Land Survey	T <u>4</u> N R <u>10</u> E	<u>M-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

\$ 7.00 MISCELLANEOUS RECORDING  
\$ 2.00 REMONUMENTATION  
8 SEP 94 3:17 P.M. RECEIPT# 134B  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS  
Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 1-5-94  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2			
3												
4	7		8		9		10		11			
5												
6	18		17		16		15		14			
7												
8	19		20		21		22		23			
9												
10	30		29		28		27		26			
11												
12	31		32		33		34		35			
13												

I, Huston K. Kennedy in a field survey on November 18, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

1817-GLO Wampler, D.S.; Set Post; 12" White Oak N30°W 51 Lns  
1979-Jones, P.S. #16045; LCRC L.7177, Pg.614 - Fnd 1/2" Iron Pipe

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1993 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" iron pipe. There are fence line extending to the North and West.

The witness points from the 1979 LCRC are still existing. They were used to recover and verify the found 1/2" iron pipe.

I accepted the found 1/2" iron pipe as the best evidence of the original corner position.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

M-5 I replaced the found 1/2" iron pipe with a 4" diameter concrete monument 36" long with 2" diameter cap stamped Oakland County Remonumentation P.S. #17623.

N35°W-20.86 ft-Set PK & Remon. Washer NE face 12" Locust  
N12°E-16.39 ft-Set PK & Remon. Washer West face 12" Basswood  
S05°W-18.80 ft-Set PK & Remon. Washer East face 20" Oak  
S20°W-34.24 ft-Set PK & Remon. Washer West face 17" Oak

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original position.

Signed by Huston K. Kennedy  
Surveyor's Michigan License No. 17623

Date June 22, 1994

