

MAY 16 1996

LAND CORNER RECORDATION CERTIFICATE

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland (County)

Located In: Orion Twp.

Corner Code #

- 1. Public Land Survey T4N R 10E M-6
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
7 MAR 95 4:08 P.M. RECEIPT# 2188
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS
Compliance with ACT 345, P.A. 1990

APPROVED ON: 2-09-95
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

- 4. Lot No.
5. Private Claims

Grid table with columns A-M and rows 1-13. A dot is marked at row 6, column M.

Huston K. Kennedy, in a field survey on December 20, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1817-GLO Wampler, D.S.; Set Post 8" White Oak N60°E 37 Links; 10" White Oak S42°W 50 Links
No recorded or unrecorded LCRCs or recorded or unrecorded surveys

Handwritten signature/initials

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 5/8" Iron Pipe .10' below road surface, 1.0' West of the centerline of Kern Road extending to the North & South with a gravel surface. I found the DNR Right of Way Marker 32.92 feet to the West of corner with a fence-tree line extending to the West. The West 1/4 corner of Section 18, T4N, R11E, (A-6) is located 77.06 feet to the North.

I accept the found 5/8" Iron Pipe as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

- M-6 to M-5 2575.52 Ft.
M-6 to M-7 2821.32 Ft.
M-6 to M-5
M-6 to A-6 (Oakland Twp.) 77.06 Ft.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-6 I replaced the found 5/8" Iron Pipe with a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623.
N51°W 35.92' Set PK & Remon. Washer NE face 10" Oak
N29°W 43.90' Set PK & Remon. Washer NE face 8" Oak
S88°E 14.55' Set PK & Remon. Washer North face 9" Oak
S85°W 21.22' Set PK & Remon. Washer North face 21" Oak
North 77.06 Feet West 1/4 corner Section 18, T4N, R11E, (A-6)

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature]
Surveyor's Michigan License No. 17623

Date December 27, 1995

