

SURVEY & REMONUMENTATION

LIBER 15212 PG 858

JAN 20 95 011172

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE

OK - T. SMITH

For corners in

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970 7.00

MISCELLANEOUS RECORDING

\$ 2.00 REMONUMENTATION

20 JAN 95 7:27 A.M. RECEIPT# 5B PAID RECORDED - OAKLAND COUNTY LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Oakland (County)	Located In:	Orion Twp.	Corner Code #/
1. Public Land Survey	T 4N R 10E		M-11
	T R		
	T R		
	T R		
2. Property Controlling in Section	S T R		
	S T R		
3. Miscellaneous Property in Sec.	S T R		
	S T R		

Compliance with ACT 345, P.A. 1990

APPROVED ON: 9-21-94 OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Huston K. Kennedy, in a field survey on October 20, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post; 6" Hickory N05*W 23 Links; 18" Black Walnut S27*W 48 Links
- 1.) 1977-Kennedy, P.S. #17623; LCRC L.7067, Pg.316 - Fnd Railroad Spike
- 2.) 1980-Buckerfield, P.S. #10868; LCRC L.7839, Pg.655 & 656 - Fnd Railroad Spike in a Monument Box
- 3.) 1987-Buckerfield, P.S. #10868; LCRC L.9803, Pg.550 - Fnd Railroad Spike in a Monument Box
- 4.) 1977-Kennedy, P.S. #17623; Unrecorded Survey - Fnd Railroad Spike, used same wit as 1977 LCRC
- 5.) 1980-Buckerfield, P.S. #10868; Unrecorded Survey - Fnd Railroad Spike, used same wit as 1980 LCRC
- 6.) 1984-Kennedy, P.S. #17623; Unrecorded Survey - Fnd Railroad Spike in a Monument Box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd Railroad Spike in a Monument Box in the centerline of Silver Bell Road, whi has a bituminou surface and 3 feet West of Kern Road to the North, Which has a gravel surface.

Witnesses from LCRC #1, 2 & 3 were used to recover and verify the location of the found Railroad Spike in a Monument Box.

I accept the found Railroad Spike in a Monument Box as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-11 I replaced the found Railroad Spike in a Monument Box with a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland Cour Remonumentation, PS #17623
- N47°E 52.89' Fnd PK & Remon. Washer PS #22445 NW face 26" Hickory
- N53°W 48.58' Fnd PK & Remon. Washer PS #22445 NE face 17" Walnut
- S42°E 52.09' Fnd PK & Remon. Washer PS #22445 SW face Power Pole
- S40°W 45.14' Fnd PK & Remon. Washer PS #22445 SE face Power Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence position of the original corner.



Signed by Huston K. Kennedy
Surveyor's Michigan License No. 17623

Date December 22, 1994