

SURVEY & REMONUMENTATION

MAY - 1 1995

LISER 15212 PG 859

JAN 20 95 0 1 1 73

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1979

For corners in
Oakland
(County)

COMMISSION

Located In: Orion Corner Code M-13
 Twp.

- | | | | |
|------------------------------------|-------------|--------------|-------------|
| 1. Public Land Survey | T <u>4N</u> | R <u>10E</u> | <u>M-13</u> |
| | T | R | |
| | T | R | |
| | T | R | |
| 2. Property Controlling in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous Property in Sec. | S | T | R |
| | S | T | R |

7.00 MISCELLANEOUS RECORDING
 2.00 REMONUMENTATION
 20 JAN 95 7:27 A.M. RECEIPT# 5B
 PAID RECORDED - OAKLAND COUNTY
 LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

OK - T. SMITH

Compliance with
 ACT 345, P.A. 1990

APPROVED ON: 9-21-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Huston K. Kennedy, in a field survey on August 1, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1817-GIO Wampler, D.S.; Set Post; 18" White Oak N15*W 27 Links; 16" White Oak S60*E 18 Links
 1.) 1992-Ward, P.S. #22445; LCRC L.12560, Pgs. 588 & 589 - End 1/2" Iron Rod

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 5/8" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation PS #22445 in a Monument Box in the centerline of Dutton Road, which has a bituminous surface extending to the West & East.

Witnesses from LCRC #1 were used to recover and verify the location of the found 5/8" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #22445 in a Monument Box.

I accepted the found 5/8" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #22445 in a Monument Box as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-13 I found a 5/8" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #22445 in a existing Monument Box
 Due North 45.48' Set PK & Remon. Washer West face Power Pole
 Due South 43.92' Set PK & Remon. Washer East face Power Pole
 S54°E 74.14' Set PK & Remon. Washer NE face 12" Ash
 S74°E 115.55' Set PK & Remon. Washer SW face 12" clump Oak

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available position of the original corner.



Signed by [Signature]
 Surveyor's Michigan License No. 17623

Date December 20, 1994