

- |     |      |   |
|-----|------|---|
| X   | 4    |   |
| .25 | 10.5 | Sec 6, 33'E of S.W. cor of N $\frac{1}{2}$ of SW $\frac{1}{4}$ Sec 6, 3/4" iron pipe; North along section line from plat mon. (south of Miller rd); East from sec line 35' to iron pipe (1960) Reported to Co. Rd Comm.   |
| 1   | 10.5 | Sec 6, SE cor of N $\frac{1}{2}$ of SW $\frac{1}{4}$ 3/4 x 30" iron pipe; N 51° 30' 9.8' Bl $\frac{1}{2}$ Tamarac; N 6° 30' E 16.9' 12" Bl $\frac{1}{2}$ Tam. + S 20° E 22.7" Bl $\frac{1}{2}$ Tam. (1960) Reported to Co. Rd Comm.<br>Center of sec 6 track spike 2" below grade & road; Spike in line with fence south (1960) Reported to Co Rd Comm. |
| 1   | 11   |   |
| 2.5 | 12   | Sec 5, NE cor of NW $\frac{1}{4}$ of NW $\frac{1}{4}$ 1" iron pipe in fence corner; fence running N, S, and W from corner. (1960) Reported to Co. Rd. Comm.   |
| 3   | 12   | Sec 5, North $\frac{1}{4}$ cor, stamped brass sec cor monument on 3/4" iron pipe about 7' N of E of old road cut; 21' S of old corner fence post; N 5° W 5.95' to blays on 20" b. oak N 85° W 6.0' to blays on 6" hickory (1960) Reported to Co Rd Comm.  |
| 4   | 12   | Sec 5, N.E. cor, iron in road; E of road grade, S 45° 10' W, 24" hickory<br>horizn spike (1960) Reported to Co. Rd Comm.  |