

**SURVEY & REMONUMENTATION**

Jan 20 95 011199

MAY - 1 1995

LIBER 15212 PG 890

OK - T. SMITH

93-1010  
For corners in

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

9.00 MISCELLANEOUS RECORDING  
2.00 REMONUMENTATION  
20 JAN 95 7:37 A.M. RECEIPT# 9B  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Oakland  
(County)

Located In: Oakland Corner Code ##

1. Public Land Survey	T	<u>4N</u>	R	<u>11E</u>	<u>A-9</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____	_____
	S	_____	T	_____	_____

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 12-29-94  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Grant J. Ward, RLS, in a field survey on December 26, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

A-9 Post, per G.L.O. Notes.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-9 Corner common to Sec. 19, 30 and Range Line, T. 4 N., R. 11 E. Set Iron Rod and Brass Cap #22445, 0.4' below Road surface, in the Centerline/Centerline of Gunn and Kern Roads. Found Iron Rod and Cap 1.69' West of the same Centerline/Centerline. We set this Corner at the Intersection of this Found Iron Rod and B-9, with M-9 and M-8 of Orion Township. This corner location is a careful and faithful re-establishment of the position of the original corner.

Previously Unrecorded in Oakland County Records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-9 Corner common to Sec. 19, 30 and Range Line, T. 4 N., R. 11 E. Set Iron Rod and Brass Cap #22445.

- N. 50° W. 53.50' Set P.K. Nail & Brass Disc #22445 in SW. face of Utility Pole.
- N. 40° E. 53.43' Set P.K. Nail & Brass Disc in NW. face of fence corner.
- S. 70° E. 62.16' Set P.K. Nail & Brass Disc #22445 in SW. face of Utility Pole.
- S. 40° E. 40.78' Found Monument on SE. corner of intersection.
- West 1.69' Found Iron Rod.
- South 135.98' Found Iron Rod (M-9, Orion Township).

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

*File*

Signed by [Signature]  
Surveyor's Michigan License No. 22445

Date December 27, 1994

