



NOVEMBER 27, 1994

Corner Code: C-2

DOSSIER FOR: THE EAST 1/4 CORNER OF SECTION 6, OAKLAND TOWNSHIP, T 4 N, R 11 E, OAKLAND COUNTY, MICHIGAN. Prepared under contract with the County of Oakland Under Act 345 of the Public Acts of 1990.

**HISTORY:**

This Township was originally surveyed by Joseph Wampler, Deputy Surveyor, in 1817.

**SPECIAL NOTES:**

After reviewing the Original GLO Notes and the transcripts, I do not believe that the original survey lines were run as documented, at least in order. Inconsistencies are evidenced by the sequence of page numbers, missing pages and inserted pages from other books in the original notebook. I expect that some lines were not measured or measured in the opposite directions indicated and that a tally (330 feet) was dropped in the fourth mile from the South line of the Township. This helps to explain large discrepancies between the GLO dimensions and what we are measuring today between Corners and noted features.

This Corner has been accepted and used since before 1985, as evidenced by a recording under Act 74 of the Public Acts of 1970.

**COLLATERAL EVIDENCE:**

This Corner lies at the intersection of the extension of the Centerlines of Harmon and Miller Roads, at the North edge of the parks and recreation trail to the east.

We searched at least 50 feet in each direction for other stakes and found none that might represent the Corner.

Aside from the GLO notes, there are no dimensions from recorded surveys, the most recent tax maps and/or other old surveys to the adjacent Government Corners.

This Corner was first recorded in 1985 by Huston K. Kennedy, in Liber 9063, Page 277, of the Oakland County Records.

**SURVEYOR'S RECOMMENDATIONS:**

Therefore, I recommend that the Peer Review Group accept this Corner as monumented, with the references as shown on the enclosed form prepared according to Act 74 of the Public Acts of 1970.

---

Grant J. Ward, R.L.S.  
License No. 22445