

SURVEY & REMONUMENTATION

LIBER **15213** PG **029**

JAN 20 95 011219

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE

OK - T. SMITH

93-1010

For corners in

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970 9.00 MISCELLANEOUS RECORDING

\$ 2.00 REMONUMENTATION
 20 JAN 95 7:42 A.M. RECEIPT# 108
 PAID RECORDED - OAKLAND COUNTY
 LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

<u>Oakland</u> <small>(County)</small>	Located In: <u>Oakland</u>	Corner Code #
1. Public Land Survey	T <u>4N</u> R <u>11E</u>	<u>D-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-28-94
 OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7		●									
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					

I, Grant J. Ward, RLS in a field survey on November 23, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-7 Post, per G.L.O. Notes.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-7 Corner common to Sec. 17 and 20, T. 4 N., R. 11 E. Found 1/2" Iron Rod, 0.4' below Road surface, 3' North of the Centerline of Buell Road. There is a tree row running North. This corner location is a careful and faithful perpetuation of the position of the original corner.

Previously Recorded in L. 7758, P. 674 (4) of Oakland County Records.

(n) Indicates the number of references that confirms this corner by dimensional tie.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-7 Corner common to Sec. 17 and 20, T. 4 N., R. 11 E. Set 5/8" Iron Rod and Brass Cap #22445 adjoining Found 1/2" Iron Rod.
- Due South 17.10' Set P.K. Nail & Brass Disc #22445 in W. face of 12" Cherry.
- S. 45° W. 31.32' Set P.K. Nail & Brass Disc #22445 in NW. face of 10" Pear Tree.
- N. 05° E. 33.43' Set P.K. Nail & Brass Disc #22445 in E. face of 34" Oak.
- N. 45° E. 15.45' Set P.K. Nail & Brass Disc #22445 in NW. face of 14" Oak.
- Due East 7.99' Found Iron Rod.
- N. 02° W. 32.87' Found Iron Rod & Cap.
- N. 02° W. 32.79' Found Iron Rod & Cap.



Signed by [Signature] Date December 27, 1994
 Surveyor's Michigan License No. 22445