

SURVEY & REMONUMENTATION

LIBER **15095** PC **018**

Nov 15 94 2 95 3 80

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Compliance with ACT 345, P.A. 1990

93-1010
For corners in **COMMISSION**

APPROVED ON: 12-22-93
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Oakland (County) Located In: Oakland Corner Code ##

1. Public Land Survey	T <u>4</u> N R <u>11</u> E	F-1
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

\$ 9.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
15 NOV 94 8:58 A.M. RECEIPT# 148
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS
OK - T. SMITH
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Grant J. Ward, RLS in a field survey on November 19, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-1 None, not set according to G.L.O. Notes.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-1 Corner common to Sec. 4 and Town Line, T. 4 N., R. 11 E. Found 1/2" Iron Rod that lines up with the Centerline of Kline and Romeo Roads and with a 2-track to the West. Replaced Found Iron Rod with Concrete Monument and Brass Cap #22445. This corner has been accepted by the peer group established under Act 345 of P.A. 1990 and although not established by an original government survey, is accepted as the best available evidence of the position of the corner.

Previously Recorded in L. 9738, P. 533 (3) of Oakland County Records.

(n) Indicates the number of references that confirm this corner by dimensional tie.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-1 Corner common to Sec. 4 and Town Line, T. 4 N., R. 11 E. Set Concrete Monument and Brass Cap #22445 that lines up with the Centerline of Kline and Romeo Roads and with a 2-track to the West.

- N. 86° W. 42.08' Found 60d Nail in S. face of 16" Ash.
- S. 30° W. 15.17' Found P.K. Nail in N.W. face of 6" Ash.
- N. 27° W. 17.09' Set P.K. Nail and Disc #22445 in E. face of 16" Ash.
- N. 13° E. 10.68' Set P.K. Nail and Disc #22445 in W. face of 6" Poplar.



Signed by [Signature] Date November 3, 1994

Surveyor's Michigan License No. 22445

93-1010