

SURVEY & REMONUMENTATION

LIBER 15095 pg 02

Nov 15 94 295382

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

OK - T. SMITH

93-1010

For corners in **COMMISSION**

Oakland
(County)

Located in: Oakland Corner Code ##

1. Public Land Survey	T	<u>4N</u>	R	<u>11E</u>	<u>G-1</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T		R
	S		T		R
3. Miscellaneous Property in Sec.	S		T		R
	S		T		R

\$ 9.00 MISCELLANEOUS RECORDING
 \$ 2.00 REMONUMENTATION
 15 NOV 94 8:58 A.M. RECEIPT# 14B
 PAID RECORDED - OAKLAND COUNTY
 LYNN D. ALLEN, CLERK/REGISTER OF DEEDS
 Compliance with
 ACT 345, P.A. 1990
 APPROVED ON: 12-22-93
 OAKLAND COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	1					
5											
6	18	17	16	15	14	1					
7											
8	19	20	21	22	23	2					
9											
10	30	29	28	27	26	2					
11											
12	31	32	33	34	35	3					
13											

I, Grant J. Ward, RLS in a field survey on November 23, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-1 Post, per G.L.O. Notes.

Handwritten signature/initials

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-1 Corner common to Sec. 3, 4 & the Town Line, T. 4 N., R. 11 E. Found 1/2" Iron Rod in Monument Box in the Centerline of Romeo Road, in line with the East edge of Road to North and also found P.K. Nail 7.0' to West. Set Iron Rod and Brass Cap #22445, adjoining Found Iron Rod. This corner has been accepted by the peer group established under Act 345 of P.A. 1990 and is a careful and faithful perpetuation of the position of the original corner.


Previously Recorded in L. 6591, P. 520 (3); L. 9738, P. 533 (4); and L. 11170, P. 544 (4) of Oakland County Records.

(n) Indicates the number of references that confirm this corner by dimensional tie.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-1 Corner common to Sec. 3, 4 & the Town Line, T. 4 N., R. 11 E. Set Iron Rod and Brass Cap #22445 in Monument Box in the Centerline of Romeo Road, in line with the East edge of Road to North and also found P.K. Nail 7.0' to West.

- S. 45° W. 31.66' Found 60d Nail in N.W. face of 30" Hickory.
- S. 30° E. 59.86' Found 60d Nail in N. face of 38" Pine.
- N. 60° W. 84.88' Found 60d Nail in S. face of 12" Pine.
- N. 10° W. 69.61' Found chiseled "+" in 3" steel fence corner.
- Due West 6.98' Found P.K. Nail.



Signed by [Signature]
 Surveyor's Michigan License No. 22445

Date November 3, 1994