

**SURVEY & REMONUMENTATION**

MAY - 1 1995

LIBER 15213 PG 115

JAN 20 95 011 262

JAN 20 95 011 262

OK - T. SMITH

93-1010  
For corners in

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

\$ 9.00 MISCELLANEOUS RECORDING  
\$ 2.00 REMONUMENTATION  
20 JAN 95 8:08 A.M. RECEIPT# 12B  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with  
ACT 345, P.A. 1990  
APPROVED ON: 12-07-94  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

Oakland (County) Located in: Oakland Corner Code #  
1. Public Land Survey T 4N R 11E I-12  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Grant J. Ward, RLS, in a field survey on November 22, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

I-12 Post, per G.L.O. Notes.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-12 Corner common to Sec. 34 and 35, T. 4 N., R. 11 E. Found Iron Rod and Cap #10863, 0.4' above swamp, 225' West of Rochester Road and 33.5' East of overhead Utility Lines. This corner location is a careful and faithful perpetuation of the position of the original corner.

Previously Recorded in L. 10345, P. 411 (3) of Oakland County Records.

(n) Indicates the number of references that confirms this corner by dimensional tie.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-12 Corner common to Sec. 34 and 35, T. 4 N., R. 11 E. Set Concrete Monument with Brass Cap #22445 in place of Found Iron Rod and Cap.

- S. 60° E. 82.63' Set P.K. Nail & Brass Disc #22445 in N. face of 20" Locust.
- N. 55° E. 94.33' Set P.K. Nail & Brass Disc #22445 in S. face of 10" Locust.
- N. 25° W. 61.57' Set P.K. Nail & Brass Disc #22445 in SW. face of Utility Pole.
- S. 57° W. 86.07' Set P.K. Nail & Brass Disc #22445 in SE. face of 8" Elm.

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

*Handwritten signature/initials*

Signed by [Signature] Date November 25, 1994  
Surveyor's Michigan License No. 22445

