

SURVEY & REMONUMENTATION

MAY - 1 1995

FORM 15095pc048

Nov 1594295395

Compliance with ACT 345, P.A. 1990

93-1010
For corners in
Oakland
(County)

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

APPROVED ON: 1-26-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

1. Public Land Survey T 4N R 11E J-5
T R
T R
T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

\$ 9.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
15 NOV 94 9:01 A.M. RECEIPT# 14B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

OK - T. SMITH

Register of Deeds Stamp & File Number

I, Grant J. Ward, RLS, in a field survey on November 11, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-5 Post, per G.L.O. Notes.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-5 Corner common to Sec. 11 & 14, T. 4 N., R. 11 E. Found Iron Rod & Cap #14097 in Swamp and in Water. Very old fence to North, West and East. No evidence of fence to South. Set 5' Iron Rod and Brass Cap #22445, adjoining Found Iron Rod. This Corner has been accepted by the peer group established under Act 345 of P.A. 1990 and is a careful and faithful perpetuation of the position of the original corner.

Previously Recorded in L. 10170, P. 058 (4), and L. 10855, P. 813 (4) of Oakland County Records.

(n) Indicates the number of references that confirm this corner by dimensional tie.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-5 Corner common to Sec. 11 & 14, T. 4 N., R. 11 E. Set 5' Iron Rod and Brass Cap #22445. Very old fence to North, West and East. No evidence of fence to South.

- N. 30° E. 20.43' Set P.K. Nail and Disc #22445 in W. face of twin 8" Elm.
- N. 71° W. 21.65' Set P.K. Nail and Disc #22445 in S. face of 8" Elm.
- S. 30° W. 15.95' Set P.K. Nail and Disc #22445 in W. face of 10" Maple.
- S. 77° E. 15.33' Set P.K. Nail and Disc #22445 in S. face of 16" Locust.



Signed by [Signature]

Date November 3, 1994

Surveyor's Michigan License No. 22445

93-1010