

SURVEY & REMONUMENTATION

JAN 20 95 OTT 265

LIBER 15213 PG 121

MAY - 1 1995

OK - T. SMITH

93-1010

LAND CORNER RECORDATION CERTIFICATE

For corners in
Oakland
(County)

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

Located In: Oakland Corner Code #

\$ 9.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
20 JAN 95 8:08 A.M. RECEIPT# 12B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-19-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

- | | | |
|------------------------------------|--------------------------|-------------|
| 1. Public Land Survey | T <u>4N</u> R <u>11E</u> | <u>J-11</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Grant J. Ward, RLS, in a field survey on February 4, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

J-11 Post, per G.L.O. Notes.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-11 Corner common to Sec. 26 and 35, T. 4 N., R. 11 E. Found 1/2" Iron Bar in the Centerline of Sheldon Road. Fence to the East and tree lines to the East and West. Bar is 0.3' below Road surface. This corner location is a careful and faithful perpetuation of the position of the original corner.

Previously Recorded in L. 6634, P. 538 (2); L. 7384, P. 847 (2); L. 8426, P. 110 (3); and L. 9063 P. 277 (4) of Oakland County Records.

(n) Indicates the number of references that confirms this corner by dimensional tie.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-11 Corner common to Sec. 26 and 35, T. 4 N., R. 11 E. Set Iron Rod and Brass Cap #22445 adjoining Found 1/2" Iron Bar.

- N. 15° E. 90.05' Set P.K. Nail & Brass Disc #22445 in NE. face of 26" Maple.
- S. 10° E. 46.35' Set P.K. Nail & Brass Disc #22445 in W. face of 32" Oak.
- N. 10° W. 48.11' Set P.K. Nail & Brass Disc #22445 in E. face of 10" Ash.
- Due West 58.15' Set P.K. Nail & Brass Disc #22445 in N. face of Power Pole.
- S. 89° W. 32.59' Found Iron Rod.



Signed by [Signature]
Surveyor's Michigan License No. 22445

Date December 20, 1994

93-1010