

SURVEY & REMONUMENTATION

JAN 20 95 011273

LIBER 15213 PG 137

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE

OK - T. SMITH

93-1010

For corners in Oakland (County)

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

\$ 9.00 MISCELLANEOUS RECORDING

\$ 2.00 REMONUMENTATION

20 JAN 95 8:10 A.M. RECEIPT# 12B PAID RECORDED - OAKLAND COUNTY LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Located in: Oakland Corner Code #

Table with 3 columns: Description, T/R, L-11. Includes Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-19-94 OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-L and rows 1-13. A dot is marked at row 11, column K.

I, Grant J. Ward, RLS, in a field survey on March 22, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-11 Post, per G.L.O. Notes.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-11 Corner common to Sec. 25 and 36, T. 4 N., R. 11 E. Found 3" Pipe in Concrete, with fence line, tree row and rock row to the West. Fence line also to the South. This corner location is a careful and faithful perpetuation of the position of the original corner.

Previously Unrecorded in Oakland County Records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-11 Corner common to Sec. 25 and 36, T. 4 N., R. 11 E. Grouted Iron Rod with Brass Cap #22445 in Found 3" Pipe in Concrete.

- S. 20° W. 18.37' Set P.K. Nail & Brass Disc #22445 in NW. face of 20" Oak.
S. 55° W. 17.50' Set P.K. Nail & Brass Disc #22445 in N. face of 18" Oak.
N. 45° W. 21.66' Set P.K. Nail & Brass Disc #22445 in SW. face of 8" Oak.
N. 10° E. 12.83' Set P.K. Nail & Brass Disc #22445 in S. face of 14" Oak.



Signed by [Signature] Surveyor's Michigan License No. 22445

Date December 20, 1994