

**SURVEY & REMONUMENTATION**

LIBER **15213** PG. **141**

JAN 20 95 011275

MAY - 1 1995

**LAND CORNER RECORDATION CERTIFICATE**

OK - T. SMITH

93-1010  
For corners in

**COMMISSION**

Filing Requirement of Act 74, Mich. P.A. 1970

\$ 9.00 MISCELLANEOUS RECORDING

\$ 2.00 REMONUMENTATION

20 JAN 95 8:10 A.M. RECEIPT# 12B  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 02-9-94  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

Oakland Located In: Oakland Corner Code ##  
(County)

- |                                    |   |           |   |            |            |
|------------------------------------|---|-----------|---|------------|------------|
| 1. Public Land Survey              | T | <u>4N</u> | R | <u>11E</u> | <u>M-1</u> |
|                                    | T |           | R |            |            |
|                                    | T |           | R |            |            |
|                                    | T |           | R |            |            |
| 2. Property Controlling in Section | S |           | T |            | R          |
|                                    | S |           | T |            | R          |
| 3. Miscellaneous Property in Sec.  | S |           | T |            | R          |
|                                    | S |           | T |            | R          |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Grant J. Ward, RLS, in a field survey on November 3, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

M-1 Post, per G.L.O. Notes.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-1 Intersection of Town and Range Line, T. 4 N., R. 11 E. Found P.K. Nail in asphalt, 0.2' below asphalt in the Centerline/Centerline of Romeo and Dequindre Roads. This corner location is a careful and faithful perpetuation of the position of the original corner.

Previously Recorded in L. 6018, P. 06 (2); L. 6634, P. 534 (2); and L. 7082, P. 440 (2) of Oakland County Records.

(n) Indicates the number of references that confirm this corner by dimensional tie.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-1 Intersection of Town and Range Line, T. 4 N., R. 11 E. Set Concrete Monument Box and 5/8" Iron Rod and Brass Cap #22445.

- S. 45° W. 46.29' Chiseled "+" in top end of 24" C.M.P.
- S. 25° E. 52.21' Set P.K. Nail & Brass Disc #22445 in SW. face of Utility Pole.
- N. 30° E. 54.61' Set P.K. Nail & Brass Disc #22445 in NW. face of Utility Pole.
- N. 25° W. 58.62' Set P.K. Nail & Brass Disc #22445 in NE. face of Utility Pole.
- S. 62° W. 86.38' Found G.P.S. Monument #10012.

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

*Handwritten signature/initials*

Signed by [Signature]

Date December 15, 1994

Surveyor's Michigan License No. 22445

93-1010

