

**SURVEY & REMONUMENTATION**

LIBER **15095pc074**

Nov 15 94 295408

MAY - 1 1995

**LAND CORNER RECORDATION CERTIFICATE**

Compliance with ACT 345, P.A. 1990

93-1010  
For corners in

**COMMISSION**

Filing Requirement of Act 74, Mich. P.A. 1970

APPROVED ON: 12-19-94  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Oakland (County) Located In: Oakland Corner Code ##

1. Public Land Survey	T <u>4N</u> R <u>11E</u>	<u>M-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

**\$ 9.00 MISCELLANEOUS RECORDING**  
**\$ 2.00 REMONUMENTATION**  
15 NOV 94 9:03 A.M. RECEIPT# 148  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS  
**OK - T. SMITH**  
Register of Deeds Stamp & File Number

I, Grant J. Ward, RLS, in a field survey on November 3, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

M-2 Post, per G.L.O. Notes.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		4
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

M-2 Corner common to Sec. 1 and Range Line, T. 4 N., R. 11 E. Found Iron Pipe 1/2", 1.50' East of Centerline of Dequindre Road and 0.45' below Road surface. Tree line to West. Set Iron Rod and Brass Cap #22445, adjoining Found Iron Pipe. This corner has been accepted by the peer group established under Act 345 of P.A. 1990 and is a careful and faithful perpetuation of the position of the original corner.

Previously Recorded in L. 6018, P. 05 (2); L. 6393, P. 58 (3); L. 6634, P. 534 (3); L. 8779, P. 763 (2); and L. 11202, P. 586 (4) of Oakland County Records.

(n) Indicates the number of references that confirm this corner by dimensional tie.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

M-2 Corner common to Sec. 1 and Range Line, T. 4 N., R. 11 E. Set Iron Rod and Brass Cap #22445, 1.50' East of Centerline of Dequindre Road. Tree line to West.

- S. 19° E. 76.60' Set P.K. Nail and Disc #22445 in W. face of wood Fence Post.
- S. 24° W. 58.51' Found Nail and Disc #17623 in E. face of 50" Oak.
- N. 10° W. 91.88' Found P.K. Nail and Disc in E. face of twin 14" Cherry.
- N. 38° E. 72.50' Set P.K. Nail and Disc #22445 in N.W. face of Utility Pole.
- S. 02° E. 71.25' Found Iron Rod.



Signed by [Signature] Date November 3, 1994

Surveyor's Michigan License No. 22445