

**SURVEY &
REMONUMENTATION**

LIBER **15095** PG **078**

Nov 15 94 295410

Compliance with
ACT 345, P.A. 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

APPROVED ON: 12-9-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

93-1010 **MAY - 1 1995**
For corners in **COMMISSION**

Oakland (County) Located In: Oakland Corner Code ##

- | | | | | | |
|------------------------------------|---|-----------|---|------------|-------|
| 1. Public Land Survey | T | <u>4N</u> | R | <u>11E</u> | M-4 |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |

\$ 9.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
15 NOV 94 9:03 A.M. RECEIPT# 14B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

OK - T. SMITH

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Grant J. Ward, RLS, in a field survey on November 3, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-4 Post, per G.L.O. Notes.

Handwritten signature/initials

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-4 Corner common to Sec. 12 & Range Line, T. 4 N., R. 11 E. Found Iron Rod 1/2", West face of Fence Post. Fence lines run East, South and West. Replaced Iron Rod with Concrete Monument and Brass Cap #22445. This corner has been accepted by the peer group established under Act 345 of P.A. 1990 and is a careful and faithful perpetuation of the position of the original corner.

Previously Recorded in L. 7550, P. 797 (4); and L. 7722, P. 867 (5) of Oakland County Records.

(n) Indicates the number of references that confirm this corner by dimensional tie.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-4 Corner common to Sec. 12 & Range Line, T. 4 N., R. 11 E. Set Concrete Monument and Brass Cap #22445, West face of Fence Post. Fence lines run East, South and West.

- S. 71° E. 24.32' Set P.K. Nail and Disc #22445 in S.W. face of 24" Cherry.
- S. 30° E. 14.28' Set P.K. Nail and Disc #22445 in S.W. face of 14" Ash.
- N. 04° E. 6.20' Set P.K. Nail and Disc #22445 in W. face of 12" Oak.
- N. 69° W. 14.41' Set P.K. Nail and Disc #22445 in S. face of 24" Cherry.



Signed by [Signature] Date November 3, 1994

Surveyor's Michigan License No. 22445