

**SURVEY &  
REMONUMENTATION**

LIBER **15095** PG **080**

Nov 15 94 295411

Compliance with  
ACT 345, P.A. 1990

MAY - 1 1995

**LAND CORNER RECORDATION CERTIFICATE**

93-1010

Filing Requirement of Act 74, Mich. P.A. 1970

APPROVED ON: 1-26-94  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

For corners in **COMMISSION**

Oakland

(County)

Located In: Oakland Corner Code ##

- |                                       |   |           |   |            |            |
|---------------------------------------|---|-----------|---|------------|------------|
| 1. Public Land Survey                 | T | <u>4N</u> | R | <u>11E</u> | <u>M-5</u> |
|                                       | T | _____     | R | _____      | _____      |
|                                       | T | _____     | R | _____      | _____      |
|                                       | T | _____     | R | _____      | _____      |
| 2. Property Controlling<br>in Section | S | _____     | T | _____      | _____      |
|                                       | S | _____     | T | _____      | _____      |
| 3. Miscellaneous<br>Property in Sec.  | S | _____     | T | _____      | _____      |
|                                       | S | _____     | T | _____      | _____      |

**\$ 2:00 MISCELLANEOUS RECORDING**  
**REMONUMENTATION**  
15 NOV 94 9:03 A.M. RECEIPT# 14B  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

OK - T. SMITH

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	I
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Grant J. Ward, RLS, in a field survey on October 25, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

M-5 Post, per G.L.O. Notes.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-5 Corner common to Sec. 12, 13 & Range Line, T. 4 N., R. 11 E. Found Iron Rod 1/2", very deteriorated. Set Iron Rod and Brass Cap #22445, adjoining Found Iron Rod, at intersection of Parks and Dequindre Roads, 7' South of Centerline of Parks Road, 3' East of Dequindre Road, 0.80' below Road surface. This corner has been accepted by the peer group established under Act 345 of P.A. 1990 and is a careful and faithful perpetuation of the position of the original corner.

Previously Recorded in L. 5982, P. 109 (3); L. 6908, P. 426 (3); L. 7550, P. 798(4); and L. 7722, P. 867 (4) of Oakland County Records.

(n) Indicates the number of references that confirm this corner by dimensional tie.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-5 Corner common to Sec. 12, 13 & Range Line, T. 4 N., R. 11 E. Set Iron Rod and Brass Cap #22445 at intersection of Parks and Dequindre Roads, 7' South of Centerline of Parks Road, 3' East of Dequindre Road.

- N. 59° W. 75.32' Found Form Nail and Disc #17623 in S. face of Utility Pole.
- N. 61° E. 59.11' Set P.K. Nail and Disc #22445 in S. face of 6" Maple.
- S. 71° E. 34.00' Found Form Nail and Disc #17623 in N. face of Utility Pole.
- S. 71° W. 37.53' Center of Stop Sign Base.
- S. 78° W. 6.90' Found 1" Iron Pipe.



Signed by [Signature]

Date November 3, 1994

Surveyor's Michigan License No. 22445

93-1010