

SURVEY & REMONUMENTATION

LIC# 15213 PG 147

JAN 20 95 011278

MAY - 1 1995

93-1010

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

OK - T. SMITH

For corners in

Filing Requirement of Act 74, Mich. P.A. 1970 9.00

MISCELLANEOUS RECORDING

\$ 2.00 REMONUMENTATION

20 JAN 95 8:11 A.M. RECEIPT# 12B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-19-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

Oakland
(County)

Located In: Oakland Corner Code #

- | | | | | | |
|------------------------------------|---|-----------|---|------------|-------------|
| 1. Public Land Survey | T | <u>4N</u> | R | <u>11E</u> | <u>M-11</u> |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Grant J. Ward, RLS, in a field survey on January 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-11 Post, per G.L.O. Notes.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-11 Corner common to Sec. 25, 36 and Range Line, T. 4 N., R. 11 E. Found 1/2" Iron Rod, 0.35' above ground surface. Very old fence to the North and West. This corner location is a careful and faithful perpetuation of the position of the original corner.


Previously Recorded in L. 8637, P. 45 (4) of Oakland County Records.

(n) Indicates the number of references that confirms this corner by dimensional tie.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-11 Corner common to Sec. 25, 36 and Range Line, T. 4 N., R. 11 E. Set Concrete Monument and Brass Cap #22445 in place of Found 1/2" Iron Rod.

- N. 85° E. 27.64' Set P.K. Nail & Brass Disc #22445 in N. face of 8" Ash.
- Due South 5.27' Set P.K. Nail & Brass Disc #22445 in W. face of 8" Maple.
- S. 60° W. 10.54' Set P.K. Nail & Brass Disc #22445 in NW. face of 12" Oak.
- Due North 36.26' Set P.K. Nail & Brass Disc #22445 in SW. face of 18" Oak.



Signed by [Signature]
Surveyor's Michigan License No. 22445

Date December 20, 1994