

MAY - 1 1995

LIBER 15213 PG 149

JAN 20 1995 011279

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

93-1010
For corners in

OK - T. SMITH

Oakland Located In: Oakland Corner Code #
(County)

1. Public Land Survey	T	<u>4N</u>	R	<u>11E</u>	<u>M-12</u>	
	T	_____	R	_____	_____	
	T	_____	R	_____	_____	
	T	_____	R	_____	_____	
2. Property Controlling in Section	S	_____	T	_____	R	_____
	S	_____	T	_____	R	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____	R	_____
	S	_____	T	_____	R	_____

\$ 9.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
20 JAN 95 8:11 A.M. RECEIPT# 12B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS
Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-19-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Grant J. Ward, RLS, in a field survey on March 22, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-12 Post, per G.L.O. Notes.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-12 Corner common to Sec. 36 and Range Line, T. 4 N., R. 11 E. Set Concrete Monument and Brass Cap #22445 in between two lane asphalt road and two lane asphalt bike path, midway and on line between M-11 and M-13. This corner location is a careful and faithful re-establishment of the position of the original corner.

Previously Unrecorded in Oakland County Records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-12 Corner common to Sec. 36 and Range Line, T. 4 N., R. 11 E. Set Concrete Monument and Brass Cap #22445.

- N. 35° W. 99.39' Set P.K. Nail & Brass Disc #22445 in SW. face of 12" Pine.
- N. 40° E. 71.40' Set P.K. Nail & Brass Disc #22445 in E. face of 16" Pine.
- Due East 141.01' Set P.K. Nail & Brass Disc #22445 in N. face of 8" Poplar.
- S. 80° E. 148.80' Set P.K. Nail & Brass Disc #22445 in N. face of 12" Poplar.
- S. 18° W. 53.52' Found Iron Rod.

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

Handwritten signature/initials

Signed by [Signature]
Surveyor's Michigan License No. 22445

Date December 20, 1994

