

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

*Oakland*

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY <u>36</u> T. <u>5</u> N. R. <u>7</u> E.		M-12, M-13	REGISTER OF DEEDS STAMP AND FILING NUMBER
2. PROPERTY CONTROLLING IN SECTION _____, T. _____, S., R. _____, E. W.			
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____, S., R. _____, E. W.			
4. LOT NO. _____, RECORDED PLAT _____			
5. PRIVATE CLAIMS _____			

I, Donald L. Bissell, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

<p>M-12 <math>E\frac{1}{2}</math> Corner Found 1" pipe w/brass cap Set by D. Scott 1962</p>	<p>M-13 SE Corner Found 1" pipe 12" below rod N13°30'W - 80.0' - 8" Hickory N58°00'E - 53.83' - 9" Hickory S47°30'E - 41.48' - 36" Hickory S46°30'W - 42.18' - 32" Hickory</p>
---	--

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p>M-12 <math>E\frac{1}{2}</math> Corner 1" pipe w/brass cap in s. edge of marsh N89°E - 9.23' - 26" Box Elder S50°E - 7.01' - 4" Elm S09°W - 79.36' - Twin Thornapple S60°W - 111.35' - 12" Willow</p>	<p>M-13 SE Corner 1" pipe N 13°30'W - 80.0' - 14" Hickory N 58°00'E - 53.83' - 14" Cherry S 47°30'E - 41.48' - 36" Hickory S 46°30'W - 42.18' - 32" Hickory</p>
---	---


SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Donald L. Bissell DATE 11-5-84  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. 18655