

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Oakland

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>25</u> T. <u>5</u> N. S., R. <u>7</u> E. W.		<u>M-11, M-10</u>
2. PROPERTY CONTROLLING IN SECTION _____, T. _____, N. S., R. _____, E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____, N. S., R. _____, E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Donald L. Bissell, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

M-11 SE Corner
Set 4" x 36" conc. mon. w/cap
on N-S fenceline and extension
of fence from west.

M-10 E $\frac{1}{2}$ Corner
Found $\frac{1}{2}$ " re-rod with stones around
with witnesses from M.D.O.T.
S20°W - 8.11' - 12" Maple
S30°E - 23.30' - 15" Elm
N35°W - 46.39' - 18" Elm
N50°E - 15.68' - 11" Elm
N85°W - 50.96' - 12" Elm

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-11 SE Corner
4" x 36" Conc. mon. w/cap
N78°E - 33.43' - 7" Cherry
S27°E - 33.43' - 14" Cherry
N03°E - 59.05' - 22" Cherry
N23°E - 16.65' - 16" Cherry

M-10 E $\frac{1}{2}$ Corner
Replaced re-rod with 3" x 10' plastic
pipe w/1" iron pipe and alum. cap in-
side and filled with conc., place
stones and poured conc. around base,
corner in swamp, old fence N-S & West.
N38°W - 9.03' - 6" Ash
N02°E - 12.73' - 5" Ash
S65°E - 9.45' - 8" Elm
S05°E - 21.94' - 5" Ash

SIGNED BY _____ DATE _____


SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Donald L. Bissell DATE _____
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. 18655