

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

1907

For corners in

Oakland Located In: Corner Code #  
(county)

1. Public Land Survey Holly Township  
T 5N R 7E A-12

T R  
T R

2. Property Controlling S T R SURVEY &  
in Section S T R RECORDED

3. Miscellaneous S T R  
Property in Sec. S T R MAR 21 2000

LIBER 20945 PAGE 502  
\$7.00 MISC RECORDING  
\$2.00 REMONUMENTATION  
01/04/2000 07:37:46 A.M. RECEIPT# 342  
PAID RECORDED - OAKLAND COUNTY  
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 8-9-99 JK  
OAKLAND COUNTY REMONUMENTATION  
REGISTER OF DEEDS STAMP & FILE NUMBER

4. Lot No. \_\_\_\_\_, Recorded Plat SECTION

5. Private Claims \_\_\_\_\_

I, James E. Kovas, in a field survey on 7-27, 99,  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points  
mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as  
required in the current manual of survey instructions of the United States Department of the Interior,  
Bureau of Land Management or by a decree of a Court of Law and/or that the corner points  
mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of  
Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented,  
re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- A-12 1816 - G.L.O., Alex Holmes, D.S., no post set
- 1994 - Wade-Trim (M-12 LCRC 1994 Genesee Remon corner) found dead 28" Oak which had log history as being the corner for M-12 Fenton accepted by Genesee Peer Review and set Genesee 30" tube and cap in tree

- Distances:
- A-12 to A-11 = 2674.53' (Wade-Trim, 1999)
  - A-12 to A-13 = 2668.27' (Wade-Trim, 1999)
  - A-12 to M-12 (Fenton) = 26.45' south (Wade-Trim, 1999)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-12 Found 1/2" iron in fenceline north-south in swamp. No record surveys to this corner found.

WITNESSES FOUND:

Found 1/2" iron in 1994 26.40' north (to A12 from M12) found 26.45'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-12 Found 1/2" iron in fence line. Removed and replaced with concrete monument cap #33138.

- WIT:
- North 24.18' Set P.K. nail w/tag #33138 10" Oak
  - N 75 E 21.42' Set P.K. nail w/tag #33138 8" Oak
  - N 55 W 20.86' Set P.K. nail w/tag #33138 8" Oak
  - S 50 W 21.79' Set P.K. nail w/tag #33138 12" Oak
  - South 23.42' F. I. East 1/2 Section 36



Signed by James E. Kovas Date 12/23/99

Surveyor's Michigan License No. 33138