

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 20945 PAGE 516
\$7.00 MISC RECORDING
\$2.00 REMONUMENTATION
01/04/2000 07:37:46 A.M. RECEIPT# 342
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

For corners in

<u>Oakland</u> (county)	Located In:	Corner Code #
1. Public Land Survey	Holly Township	T <u>5N</u> R <u>7E</u> <u>C-9</u>
		T ___ R ___ <u>SURVEY 8</u>
		T ___ R ___ <u>REESTABLISHMENT</u>
		T ___ R ___
2. Property Controlling in Section	S ___ T ___	R ___ <u>MAR 21 2000</u>
3. Miscellaneous	S ___ T ___	R ___
Property in Sec.	S ___ T ___	R ___ <u>SECTION</u>

REGISTERED
ACT OF MICH. 1999
MOVED ON 6-16-99 JS
OAKLAND COUNTY REGISTER OF DEEDS
1100 JEFFERSON ST. S.W.
ANN ARBOR, MI 48106
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, James E. Kovas, in a field survey on May 5, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- C-9
1816 - G.L.O., Alex Holmes, D.S., set post
1990 - Chris Newman #24607, no monument described

- Distances:
- C-9 to C-8 = 2705.38' (Wade-Trim, 1999)
 - C-9 to D-9 = 2663.95' (Wade-Trim, 1999)
 - C-9 to C-10 = C-10 is in a Lake
 - C-9 to C-11 = 5224.74' (Wade-Trim, 1999)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- C-9 Found concrete monument in fence line to North and West.


No witnesses found, but the DNR office that the crew talked to led them to this monument and said it was the section corner. This corner is located in Seven Lakes State Park.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-9 Found concrete monument in North and West fence line in woods (no cap was placed on).

- WIT:
- West 32.10' Set 60d nail w/tag #33138
 - North 29.75' Set 60d nail w/tag #33138
 - S 40 E 35.15' Set 60d nail w/tag #33138
 - S 60 W 11.85' Set 60d nail w/tag #33138

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11							
5												
6	18	17	16	15	14							
7												
8	19	20	21	22	23							
9												
10	30	29	28	27	26							
11												
12	31	32	33	34	35							
13												



Signed by James E. Kovas Date 12/22/99

Surveyor's Michigan License No. 33138