

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1925

For corners in

LIBER 20945 PAGE 520
\$7.00 MISC RECORDING
\$2.00 REMONUMENTATION
01/04/2000 07:37:46 A.M. RECEIPT# 342
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Oakland Located In: Corner Code #
(county)
1. Public Land Survey Holly Township
T 5N R 7E D-1
T R SURVEY &
T R RE-ESTABLISHMENT
T R
2. Property Controlling S T R
in Section S T R MAR 21 2000
3. Miscellaneous S T R
Property in Sec. S T R SECTION

APPROVED ON: 7-8-99
OAKLAND COUNTY REMONUMENTATION
PEER GROUP CERTIFICATION
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, James E. Kovas, in a field survey on March 30, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-1
1816 - G.L.O., Alex Holmes, D.S., set post

Distances: D-1 to C-1 = 2598.85' (Wade-Trim, 1999)
D-1 to D-13 = 70.65' West (Wade-Trim, 1999)
D-1 to E-1 = 2598.85' (Wade-Trim, 1999)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-1 Set concrete monument with cap #33138.

As per the Oakland County Peer Review 8/8/99, C-1 will be set on line between C-13 (the concrete post) and D-13 at 1/2 the distance from C-1 to E-1.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-1 Set concrete monument with cap #33138.

WIT: S 45 W 11.53' Nail w/tag #33138 NE face 4" Elm
West 70.65' Concrete monument Genesee County
N 80 W 38.97' Nail w/tag #33138 4" Elm NE face
N 25 W 90.55' Nail w/tag #33138 SW face 5" Elm

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2			
3												
4	7		8		9		10		11			
5												
6	10		17		16		15		14			
7												
8	19		20		21		22		23			
9												
10	30		29		28		27		26			
11												
12	31		32		33		34		35			
13												

Signed by James E. Kovas Date 12/23/99

Surveyor's Michigan License No. 33138

