

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 20945 PAGE 524
MISC RECORDING
\$2.00 REMONUMENTATION
01/04/2000 07:37:46 A.M. RECEIPT# 342
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

For corners in

Oakland Located In: Corner Code #
(county)
Holly Township
1. Public Land Survey T 5N R 7E D-9
T R
T R
T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

SURVEY &
REMONUMENTATION

MAR 21 2000

SECTION

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, James E. Kovas, in a field survey on July 29, 1998
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
D-9
1816 - G.L.O., Alex Holmes, D.S., set post

Distances: D-9 to E-9 = 2636.18' (Wade-Trim, 1998)
D-9 to C-9 = 2663.95' (Wade-Trim, 1999)


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
D-9 Found concrete monument in north-south-west fence row.

This corner is on State Park land. The DNR ranger at the site said that this monument has been the section corner for as long as he can remember. We recommend that this corner be accepted as found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
D-9 Found concrete monument. Placed cap #33138.

WIT: South 8.62' Tag 333138 12" White Oak
S 20 E 14.19' Tag #33138 28" Oak
North 9.35' Tag #33138 14" Oak
West 18.49' Tag #33138 12" Ash

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												



Signed by James E. Kovas Date 12/23/99

Surveyor's Michigan License No. 33138 FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975