

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1930

For corners in

LIBER 20945 PAGE 525
\$7.00 MISC RECORDING
\$2.00 REMONUMENTATION
01/04/2000 07:37:46 A.M. RECEIPT# 342
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

<u>Oakland</u> (county)	Located In:	Corner Code #
	Holly Township	
1. Public Land Survey	T <u>5N</u> R <u>7E</u>	<u>D-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____	<u>SURVEY & REMONUMENTATION</u>
3. Miscellaneous Property in Sec.	S _____ T _____	<u>MAR 21 2000</u>

Complies with
ACT 74, P.A. 1970

APPROVED ON: 9-8-99 SIL
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat SECTION

5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K
2	6		5		4		3		2	
3										
4	7		8		9		10		11	
5										
6	13		17		16		15		14	
7										
8	19		20		21		22		23	
9										
10	30		29		28		27		26	
11										
12	31		32		33		34		35	
13										

I, James E. Kovas, in a field survey on March 31, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- D-11
- 1816 - G.L.O., Alex Holmes, D.S., set post
- 1980 - Grant Ward #22445 (LCRC Liber 7947, Page 876) found iron rod from previous surveys
- 1979 - John Albright #10057 (LCRC Liber 7455, Page 864) found 1/2" iron rod
- 1991 - Brad Thompson #23828 (LCRC Liber 11922, Page 505, Survey Liber 11913, Page 546) found 1/2" iron in marsh

Distances:

- D-11 to E-11 = 2640.14' (Wade-Trim, 1999)
- D-11 to E-11 = 2640.00 (Thompson, 1990)
- D-11 to C-11 = 2652.56' (Wade-Trim, 1999)
- D-11 to C-11 = 2652.76' (Grant Ward, 1979)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-11 Found iron in marsh.

Found iron as SW corner of parcel 5 of Thompson 1990 survey.
1846.09' (M) east 1845.97' (R) Thompson Liber 11913, Page 546


WITNESSES FOUND:

East 30' +/- from Shiawasee River with steel post beside it found 30+/-
S 15 E 109.25' To set dbl. nail w/bft fl West 6" Elm found 109.04'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-11 Found 1/2" iron, reset wwith remon cap #33138.

WIT: N 65 E 146.10' Set mag nail w/tag #33138 2" Srub
S 25 E 109.04' Set mag nail w/tag #33138 8" Dead tree
South 96.08' Set mag nail w/tag #33138 8" Elm quad
West 21.62' Set mag nail w/tag #33138 2" Srub



Signed by James E. Kovas Date 12/22/99

Surveyor's Michigan License No. 33138