

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1931

LIBER 20945 PAGE 526
\$7.00 MISC RECORDING
\$2.00 REMONUMENTATION
01/04/2000 07:37:46 A.M. RECEIPT# 342
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CABELL, CLERK/REGISTER OF D

For corners in

<u>Oakland</u> (county)	Located In:	Corner Code #
	Holly Township	
1. Public Land Survey	T <u>5N</u> R <u>7E</u>	<u>D-13</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

10.28.99 JS

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, James E. Kovas, in a field survey on December 20, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K
2	6	5	4	3	2					
3										
4	7	8	9	10	11					
5										
6	16	17	18	15	14					
7										
8	19	20	21	22	23					
9										
10	30	29	28	27	26					
11										
12	31	32	33	34	35					
13										

A. Description of original monument and accessories and/or subsequent restoration:

- D-13
- 1816 - G.L.O., Alex Holmes, D.S., set post
- 1979 - John Albright #10057 (LCRC Liber 7455, Page 864) found 1/2" rerod
- 1995 - Grant Ward #22445 (LCRC Liber 16095, Page 684) iron

Distances: D-13 to C-13 = 2640.98' (Wade-Trim, 1998)
 D-13 to E-13 = 2640.87' (Wade-Trim, 1998)
 D-13 to E-13 = 2640.88' (Ward, 1995)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13 Found 1" solid bar in road with Grant Ward cap.


WITNESSES FOUND:

N 25 E 13.64' to Ward tag in mailbox post found 13.64'
 S 70 E 64.00' to Ward tag in 18" Maple found 64.00'
 S 60 W 85.70' to Ward tag in 33" Willow found 85.77'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13 Found 1" solid bar in road with Grant Ward cap. Removed and replace with 5/8" monument and cap #33138.

WIT: S 70 E 64.04' Set P.K. nail w/tag #33138 18" Willow
 N 40 E 33.17' Set P.K. nail w/tag #33138 6" Cluster
 North 75.02' Set P.K. nail w/tag #33138 18" Pine
 S 60 W 85.74' Set P.K. nail w/tag #33138 33" Willow



Signed by James E. Kovas Date 12/23/99

Surveyor's Michigan License No. 33138