

LIBER 20945 536

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1941

For corners in

LIBER 20945 PAGE 536
\$7.00 MISC RECORDING
\$2.00 REMONUMENTATION
01/04/2000 07:37:46 A.M. RECEIPT# 34
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF

ACT 74, P.A. 1970

8-23-98 35

Register of Deeds Stamp & File Number

Oakland Located In: Holly Township Corner Code #
(county)
1. Public Land Survey T 5N R 7E E-10
T R
T R
T R
2. Property Controlling S T R
in Section S T R SURVEY &
3. Miscellaneous S T R RE-ESTABLISHMENT
Property in Sec. S T R MAR 21 2000

4. Lot No. _____, Recorded Plat _____ SECTION _____

5. Private Claims _____

I, James E. Kovas, in a field survey on July 27, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
2		6		5		4		3		2		
3												
4		7		8		9		10		11		
5												
6		16		17		18		15		14		
7												
8		19		20		21		22		23		
9												
10		30		29		28		27		26		
11												
12		31		32		33		34		35		
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- E-10 1816 - G.L.O., Alex Holmes, D.S., set post
- 1972 - John Albright #10057 (LCRC Liber 6002, Page 508) found monument box
- 1978 - John Albright #10057 (LCRC Liber 11533, Page 437 and Liber 11337, Page 232) found 1/2" iron monument box

Distances: E-10 to E-9 = 2645.11' (Wade-Trim, 1999)
E-10 to E-9 = 2645.08' (Newman, 1988)
E-10 to E-11 = 2631.36' (Wade-Trim, 1999)


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-10 Found "T" iron in monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-10 Found "T" iron in monument box. Reset 1/2" iron and remon cap #33138.

WIT: N 33 E 92.37' Set P.K./tag #33138 West face power pole
N 15 W 134.32' Set P.K./tag #33138 East face 18" Twin Oak
S 10 E 113.20' Set P.K./tag #33138 West face 28" Maple
West 46.64' Set P.K./tag #33138 North face 10" Maple
West 33.02' Found 1/2" B/C #24807



Signed by James E. Kovas Date 12/23/99

Surveyor's Michigan License No. 33138