

LIBER 20945 542
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

1947

For corners in

Oakland <small>(county)</small>	Located In:	Corner Code #	
	Holly Township		
1. Public Land Survey	T <u>5N</u> R <u>7E</u>	<u>F-5</u>	
	T ___ R ___	___	
	T ___ R ___	___	
	T ___ R ___	___	
2. Property Controlling in Section	S ___ T ___	R ___	SURVEY & RECORDATION
3. Miscellaneous Property in Sec.	S ___ T ___	R ___	MAR 21 2000

LIBER 20945 PAGE 542
 \$7.00 MISC RECORDING
 \$2.00 REMONUMENTATION
 01/04/2000 07:37:46 A.M. RECEIPT# 34
 PAID RECORDED - OAKLAND COUNTY
 G. WILLIAM CADDELL, CLERK/REGISTER OF

4-15-99 53

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____ **SECTION** _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K
2	6	5	4	3	2						
3											
4	7	8	9	10	11						
5						●					
6	18	17	16	15	14						
7											
8	19	20	21	22	23						
9											
10	30	29	28	27	26						
11											
12	31	32	33	34	35						
13											

I, James E. Kovas, in a field survey on March 29, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-5
 1816 - G.L.O., Alex Holmes, D.S., set post

- Distances:
- F-5 to E-5 = 2643.40' (Wade-Trim, 1999)
 - F-5 to G-5 = 2646.50' (Wade-Trim, 1999)
 - F-5 to G-5 = 2646.73' (Newman, 1993)
 - F-5 to F-7 = 5259.52' (Wade-Trim, 1999)
 - F-5 to F-7 = 5259.16' (Newman, 1993)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-5 Found 2" pipe.

WITNESSES FOUND:

- | | | | | |
|--------|--------|-----------------|-------|--------|
| N 45 E | 16.45' | to 18" Oak | found | 16.46' |
| N 15 E | 22.78' | to 18" Oak | found | 22.80' |
| South | 32.00' | to 12" Twin Ash | found | 32.04' |
| West | 30.85' | to 12" Twin Oak | found | 30.82' |

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-5 Found 2" Iron pipe in fence line North, South, and West. Removed and replaced concrete monument in rock pile.

- WIT:
- N 60 E 16.92' Set P.K. nail w/tag #33138
 - S 10 W 32.05' Set P.K. nail w/tag #33138
 - West 30.84' Set P.K. nail w/tag #33138
 - N 37 W 14.54' Set P.K. nail w/tag #33138



Signed by James E. Kovas Date 12/22/99

Surveyor's Michigan License No. 33138