

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1951

LIBER 20945 PAGE 546
\$7.00 MISC RECORDING
\$2.00 REMONUMENTATION
01/04/2000 07:37:46 A.M. RECEIPT#
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER

For corners in

Oakland Located in: Holly Township Corner Code #
(county)
1. Public Land Survey T 5N R 7E F-13
T R
T R
T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

10-28-98 JS
Register of Deeds Stamp & File Number

SECTION

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K
2	6	5	4	3	2						
3											
4	7	8	9	10	11						
5											
6	18	17	16	15	14						
7											
8	19	20	21	22	23						
9											
10	30	29	28	27	26						
11											
12	31	32	33	34	35						
13											

I, James E. Kovas, in a field survey on September 9, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-13
1816 - G.L.O., Alex Holmes, D.S., set post
1995 - Chris Newman #24607 (Survey Liber 16003, Page 385) found 2" pipe

Distances: F-13 to G-13 = 2651.65' (Wade-Trim, 1999)
F-13 to G-13 = 2651.09' (Newman, 1995)
F-13 to E-13 = 2623.67' (Wade-Trim, 1998)
F-13 to F-1 (Rose) = 70.70' west (Wade-Trim, 1999)
F-13 to F-1 (Rose) = 70.60' west (Newman, 1995)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-13 Found 2" pipe.


WITNESSES FOUND:

N 60 E 55.95' to 4" Birch found 56.11'
N 10 W 16.95' to gate post found 16.20'
N 70 E 56.11' to 12" Ash found 56.11'
N 10 E 21.24' to steel post found 21.40'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13 Found 2" iron pipe. Removed and replaced with concrete monument.

WIT: N 80 E 56.13' Set nail w/tag #33138 8" Ash
N 10 E 21.22' Centerline Fence post
N 20 W 16.99' Set nail w/tag #33138 wood gate post



Signed by James E. Kovas

Date 12/22/98

Surveyor's Michigan License No. 33138