

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland Located In: Holly Township Corner Code # H-7  
(county)  
1. Public Land Survey T. 5N R. 7E  
T. R.  
T. R.  
T. R.  
2. Property Controlling S. T. R. SURVEY & RE-MONUMENTATION  
in Section S. T. R.  
3. Miscellaneous S. T. R.  
Property in Sec. S. T. R. MAR 21 2000

1966

LIBER 20945 PAGE 561  
\$7.00 MISC RECORDING  
\$2.00 REMONUMENTATION  
01/04/2000 07:37:46 A.M. RECEIPT# 342  
PAID RECORDED - OAKLAND COUNTY  
G. WILLIAM CABDELL, CLERK/REGISTER OF DEED

ACT 342, P.A. 1990

PROVED ON: 1-5-99 JS  
OAKLAND COUNTY REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat SECTION  
5. Private Claims \_\_\_\_\_

I, James E. Kovas, in a field survey on December 15, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-7  
1816 - G.L.O., Alex Holmes, D.S., set post

Distances: H-7 to I-7 = 2544.48' (Wade-Trim, 1998)

H-7 to G-7 = 2596.05' (Wade-Trim, 1998)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-7 Found 1/2" rerod. Rerod was found in a wire fence which runs north and south.

WITNESSES FOUND:

North 9.95' to 15" Cherry found 10.05'  
N 30 E 25.75' to 8" Twin Crab fell over

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-7 Found 1/2" Iron In fence line. Removed and replaced with concrete monument cap #33138.

WIT: North 10.06' Set nail w/tag #33138 14" Cherry  
S 67 E 30.39' Set nail w/tag #33138 8" Maple  
S 42 W 23.06' Set nail w/tag #33138 16" Oak  
West 18.15' Set nai w/tag #33138 10" Oak

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	1						
5												
6	16	17	18	15	14	1						
7												
8	19	20	21	22	23	2						
9												
10	30	29	28	27	26	2						
11												
12	31	32	33	34	35	3						
13												

Signed by James E. Kovas Date 12/22/99

Surveyor's Michigan License No. 33138

