

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 21023 PAGE 534
\$7.00 MISC RECORDING
\$2.00 REMONUMENTATION
01/26/2000 09:06:21 A.M. RECEIPT# 6359
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

For corners in

Oakland
(county)

Located In: Corner Code #

- 1. Public Land Survey T 5N R 7E K-6
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

SURVEY & RECORDATION
MAR 21 2000

Compliance with ACT 345, P.A. 1990
APPROVED ON: 5-12-99 55
OAKLAND COUNTY REMONUMENTATION BOARD COMMITTEE
Register of Deeds Stamp & File Number

SECTION

- 4. Lot No. Recorded Plat
5. Private Claims

I, James E. Kovas, in a field survey on January 4, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-K and rows 2-13. Contains numbers 6-36.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-6
1816 - G.L.O., Alex Holmes, D.S., set post

- Distances: K-6 to K-7 = 2630.80' (Wade-Trim, 1999)
K-6 to K-7 = 2640.00' (40 chains GLO)
K-6 to K-5 = 2630.80' (Wade-Trim, 1999)
K-6 to K-5 = 2640.00' (40 chains GLO)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-6 No monument found. No possession found. Corner falls in swamp.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-6 Set concrete monument in woods with location per peer location w/tag #33138.

- WIT: N 10 E 8.53' Set P.K. nail w/tag #33138 10" Oak
N 80 E 33.96' Set P.K. nail w/tag #33138 18" Oak
S 15 W 18.59' Set P.K. nail w/tag #33138 10" Cherry
N 45 W 12.78' Set P.K. nail w/tag #33138 12" Oak North face



Signed by James E. Kovas

Date 1/17/00

Surveyor's Michigan License No. 33138