

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

24604

LIBER 21023 PAGE 535  
\$7.00 MISC RECORDING  
\$2.00 REMONUMENTATION  
01/26/2000 09:06:21 A.M. RECEIPT# 6359  
PAID RECORDED - OAKLAND COUNTY  
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

For corners in

Oakland Located In: Corner Code #  
(county)

1. Public Land Survey Holly Township  
T 5N R 7E K-10  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_  
3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 5-12-99 53  
OAKLAND COUNTY REMONUMENTATION  
REGISTER OF DEEDS STAMP & FILE NUMBER

SURVEY &  
REMONUMENTATION  
MAR 21 2000

4. Lot No. \_\_\_\_\_, Recorded Plat SECTION

5. Private Claims \_\_\_\_\_

I, James E. Kovas, in a field survey on January 4, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11							
5												
6	18	17	16	15	14							
7												
8	19	20	21	22	23							
9												
10	30	29	28	27	26							
11												
12	31	32	33	34	35							
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-10  
1816 - G.L.O., Alex Holmes, D.S., set post

Distances: K-10 to K-9 = 2609.28' (Wade-Trim, 1999)  
K-10 to K-9 = 2640.00' (40 chains, GLO)  
K-10 to K-11 = 2609.28' (Wade-Trim, 1999)  
K-10 to K-11 = 2640.00' (40 chains, GLO)


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-10 No monument found.  
No possession found.  
No recorded or unrecorded survey documents found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-10 Set concrete monument in swamp per Peer location w/tag #33138.

WIT: N 20 E 114.42' Set P.K. nail w/tag #33138 8" Maple  
N 78 E 81.48' Set P.K. nail w/tag #33138  
S 88 W 73.17' Set P.K. nail w/tag #33183  
S 46 W 62.08' Set P.K. nail w/tag #33138 12" Oak



Signed by James E. Kovas

Date 1/17/00

Surveyor's Michigan License No. 33138